

The words **FORGINGS** or **CASTINGS**, **IRON** or **STEEL**, should be struck out as may be required.

Lloyd's Register of Shipping.

Report on Vessel No. 21313 Port Keith


No. 12799.

SHIP ~~FORGINGS OR~~ CASTINGS.

I have to report that the undermentioned ~~Iron or Steel Forgings or Castings~~, manufactured by Messrs Steel Company of Scotland Ltd of Hallside Lanarkshire for the Vessel No. 335, being built by Messrs H. R. Ltd of Luth have been inspected by me as set forth below and found to be, so far as can be seen, Sound.

Mark on Forgings or Castings.

Lloyd's  
No. 12799 Test No.  
Wd. 29.6.43



	STERN FRAME.	<del>RUDDER FRAME.</del>	<del>STEM.</del>
Material* ... ..	Open Hearth Steel		
How made ... ..	Cast		
If annealed ... ..	No		
Dimensions ... ..	To pattern		
Progress on Inspection ...	Machined to Specification		
Dates when Inspected ...	4/6/43 - 29/6/43.		
CASTINGS.			
Tests on Standard Test Pieces.	Test No. 23.		
Tensile Test—			
Ultimate Tensile. Tons per sq. in. ...	33.2.		
Yield Point Tons per sq. in. ...			
Extension per cent. on 3 inches ...	26.0%		
Red. of Area % ... ..			
Cold Bending Test—			
Angle before fracture ...	120° NF		
Drop Test			
Height from ground ...	7 feet		
Hammering Test—			
If made according to Rules and found satisfactory ...	Yes.		

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £ monthly account New Classed Vessel.

To be paid at \_\_\_\_\_

\*If of Iron, state whether scrap or puddled Iron. If of Steel, state whether made on the Open Hearth process.

