

E.1 OCT 1948

Lloyd's Register of Shipping.

Ship's Name M/V "JALTA" (Harland & Wolff No 1373) Official No. ✓

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in Belfast September 1948.

An additional hatchway has been fitted on the upper deck inside forecastle and leading to fore hold. Size of hatchway 2'-0" x 18" with 9" BA coaming .44" thick, closed by steel hinged watertight lid secured by toggle bolts.

Watertight door entrance in bridge aft end leading to Gyro Room now removed and opening plated over. A new trunkway access from bridge deck house has been fitted. Size of trunkway 2'-7" x 2'-3" x .30 plating. Door opening 4'-6" x 20" x 15" sill closed by 2" thick solid wood hinged door operated from both sides.

A.S.G.
Belfast 16/9/48.

*Held
16/9/48*

4 OCT 1948