

s.s. "DELUNGRA"

This ship was built by N.S.W. Government Eng. & Shipbuilding., at Newcastle, N.S.W. in 1947-10 and then classed #100A1.

A SPECIAL SURVEY was due 7,56.

The class was expunged for non-compliance with Regulations 21.7.60.

At the time of expunging the class was subject to stern plating, etc. being examined and dealt with as necessary and to permanent repairs to indented 'G' strake plating etc. (s.s.f), indented shell plate F.2 (p.s.f) also bulwark plating etc. abreast Nos. 1 & 2 hatchways (s.s.) by next Special Survey, and to indented forecastle head side plating (s.s.) being dealt with as found necessary at the next drydocking. There was also a S.R.L.Appendix Note - Indents in 'J' strake plating (s.s.f).

In a letter dated 22.8.60 the Hong Kong Surveyors advise that the ship has been sold and the new Owners request Reclassification.

IT IS SUBMITTED the Owners, through the Hong Kong Surveyors, be advised that for Reclassification it will be necessary for:-

1. The requirements of a SPECIAL SURVEY (C) to be complied with including the drilling of the structure in such parts where signs of wastage are evident.
2. Any major repairs which have been or are to be effected to the structure since the ship was disclassed to be specially examined in order to ascertain the character of the workmanship and confirm that the materials used are in accordance with the Rules.
3. Structural alterations affecting the longitudinal and/or transverse strength of the ship which may be required at this time should be carried out in accordance with plans to be previously approved.
4. Structural alterations which may have been carried out since the ship was disclassed to be specially examined in order to ascertain the character of the workmanship and confirm that all, including materials, conform to Rule requirements, and
5. full particulars of the equipment on board, including weights, tests and condition of anchors also length, diameter, tests and condition etc. of chain cable to be furnished for consideration.

30.11.60.

For cable & etc H.K. (14) 30.11.60

010484-010494-0332