

LT NYMDIBLE, NEW YORK (U.S.A.) (12.1.60.)

APURE REURCAB THICKNESSES IN HUNDREDTHS OF AN INCH MIDSHIP HALF
LENGTH SHELL KEEL SIXTYEIGHT A TO E INCLUSIVE FORTYSEVEN F G
FORTYFIVE H FORTYFIVE SIXTY AT POOP FRONT FIFTYFOUR BRIDGE ENDS
DOUBLING FORTYFIVE STOP DOUBLING FORTYSEVEN ON A B D STRAKES UPPER
DECK STRINGER FORTYFOUR STOP FIFTYFOUR IN WAY OF BRIDGE STOP DECK
FORTYTWO BRIDGE DECK STRINGER THIRTYEIGHT INBOARD FIRST THIRTY
SECOND FIFTYSIX STOP FIFTYTWO AT NUMBER ONE TANK THIRD FORTY
CENTRELINE FIFTYSIX STOP FIFTYTWO AT NUMBER ONE TANK STOP MIDSHIP
SECTION FOLLOWS

COMMITTEE

© 2021



Lloyd's Register
Foundation

010484-010494-0385