

S.S. "CHLORIS" ex "EIDER".

Dimensions: 250.7 x 37.4 x 15.1

Equipment letter "p".

This vessel was built to class with the Germanischer Lloyd, and is at present under survey with a view to class with this Society.

The equipment required by the Rules and that on Board the vessel are as follows:-


<u>Rule.</u>	<u>On board.</u>
3 bower anchors (stockless) total weight 4420 kgs.	3 bower anchors (stockless) total weight 4500 kgs.
1 stream anchor 394 kgs, ex stock.	1 stream 504 kgs. ex stock.
440 metres of 41 m/m stud chain cable	1 kedge 255 kgs. ex stock. 383 <del>440</del> metres of 40 m/m stud chain
135 metres 95 m/m steel wire	138 metres 93 m/m steel wire
165 " 83 m/m " "	165 " 76 m/m " "
2 at 152 metres 57 m/m stl. wire)	4 at 63 m/m steel wire
2 at 127 " " " " )	

It will be observed that the weight of the anchors on board is greater than required by the Rules, but that the chain cable although ~~of~~ approximately <sup>of</sup> the same diameter is 57 metres deficient in length. The stream steel wire and the towline could be accepted in view of the size of the hawsers, provided the length of the latter is equal to that required by the Rules, and the Surveyors should satisfy themselves on this point.

It is submitted that provided an additional 30 (55 metres) fathoms of 1 9/16" (40 m/m) stud chain cable be supplied in order to make the weight of cable equivalent to that required by the Rules, the equipment will merit approval for the figure 1.

L: 24.7.23  
ansd 31/2  
13 certs.

23/1/7



© 2021

WJ

MS

30.7.23.

010509 - 010518 - 0048