

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Ship's Name CANTIERI CELLI S.A.	Official Number	Nationality and Port of Registry	Gross Tonnage	Date of Build	Port of Survey
Des. 1351					Date of Survey 13-8-48
Moulded Dimensions: Length 80' Breadth 15.75' Depth 6.14'					Surveyor's Signature E. J.
Moulded displacement at moulded draught = 85 per cent. of moulded depth _____ tons					Particulars of Classification
Coefficient of fineness for use with Tables assumed .68					

DEPTH FOR FREEBOARD (D).

Moulded depth ... **6.14**

Stringer plate **.20** ... **.02**

Sheathing on exposed deck

$T \left(\frac{L-S}{L} \right) =$

Depth for Freeboard (D) = **6.16**

DEPTH CORRECTION.

(a) Where D is greater than Table depth
(D-Table depth) R = **(6.16 - 5.33) .615 = + .51"**

(b) Where D is less than Table depth (if allowed)
(Table depth-D) R =

If restricted by superstructures

ROUND OF BEAM CORRECTION.

Moulded Breadth (B) **15.75'**

Standard Round of Beam = $\frac{B \times 12}{50} =$ **3.78"**

Ship's Round of Beam **1180 mm** = **7.09"**

Difference **3.31**

Restricted to

Correction = $\frac{\text{Diff.}}{4} \times \left(1 - \frac{S_1}{L} \right) = \frac{3.31}{4} \times .812 = -.67"$

DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S ₁)	Height	Height Correction	Effective Length (E)
Poop enclosed ...	20.47	20.47	4.41	4.41/6.6	15.04
„ overhang ...					
R.Q.D. enclosed ...					
„ overhang ...					
Bridge enclosed ...					
„ overhang aft ...					
„ overhang forward ...					
Fore enclosed ...					
„ overhang ...					
Trunk aft Nil to Keel ...					
„ forward ...					
Tonnage opening aft ...					
„ „ forward ...					
Total ...	20.47	20.47			15.04

Standard Height of Superstructure **6.0'**

„ „ R.Q.D. **14.0"**

Deduction for complete superstructure **14.0"**

Percentage covered $\frac{S}{L} =$ **25.59** ✓

„ „ $\frac{S_1}{L} =$ **18.80** ✓

Percentage from Table, Line A. **9.40** ✓

(corrected for absence of forecastle (if required)) **4.40** ✓

Percentage from Table, Line B.

(corrected for absence of forecastle (if required))

Interpolation for bridge less than .2L (if required)

Deduction = **14.0 × .044 = -.62"**

SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product
A.P. ...	18.00	1		18.00	9.00	9.00	1		9.00
$\frac{1}{6}L$ from A.P. ...	8.01	4		32.04	1.00	1.00	4		4.00
$\frac{2}{6}L$ „ ...	1.98	2		3.96	-2.00	-2.00	2		-4.00
Amidships ...	-	4		-	-	-	4		-
$\frac{4}{6}L$ from F.P. ...	3.96	2		7.92	7.00	3.96	2		7.92
$\frac{5}{6}L$ „ ...	16.02	4		64.08	20.00	16.02	4		64.08
F.P. ...	36.00	1		36.00	35.00	36.00	1		36.00
Total ...				162.00					117.00

Correction = $\frac{\text{Difference between sums of products}}{18} \left(.75 - \frac{S}{2L} \right) =$ **$\frac{45}{18} \times (.75 - .1279) = + 1.56'$**

If limited on account of midship superstructure.

Mean actual sheer aft = **< .5** ✓

Mean standard sheer aft =

Mean actual sheer forward = **> 1** ✓

Mean standard sheer forward =

Length of enclosed superstructure forward of amidships = **nil**

„ „ aft of „ = **nil**

Deduction for Tropical Freeboard.**Addition for Winter and Winter North Atlantic Freeboard.**

Depth to Freeboard Deck = **6.16**

Summer freeboard = **.73**

Moulded draught (d) = **5.43**

Deduction for Tropical freeboard and addition for

Winter freeboard = $\frac{d}{4}$ inches =

Addition for Winter North Atlantic Freeboard (if required)=**Deduction for Fresh Water.**

Displacement in salt water at summer load water line

$\Delta =$

Tons per inch immersion at summer load water line

T =

Deduction = $\frac{\Delta}{40 T}$ inches

TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient

Depth Correction ... **.51**

Deduction for superstructures ... **.62**

Sheer correction ... **1.56**

Round of Beam correction ... **.67**

Correction for Thickness of Deck amidships ...

Other corrections, scantlings, etc. ...

+	-
.51	.62
1.56	.67
2.07	1.29

Summer Freeboard = **8.78** ✓**SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, ~~Woolly~~ Steel, Deck :-**

Tropical Fresh Water Line above Centre of Disc ...

Fresh Water Line „ „ ...

Tropical Line „ „ ...

Winter Line below „ „ ...

Winter North Atlantic Line „ „ ...

Tropical Fresh Water Freeboard ...

Fresh Water „ „ ...

Tropical „ „ ...

Winter „ „ ...

Winter North Atlantic „ „ ...