

## Lloyd's Register of Shipping.

Ship's Name "MOAMOA"

Official No. 159465

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in Oct 1937 (when built)

Eight manholes now cut in upper deck for access  
to side tanks for carrying molasses (one to each tank)  
fitted with oiltight steel covers; those in forward well  
having strongly constructed steel coamings 30" in height.

Eight sidelights <sup>(P+S.)</sup> in Bridge tween decks now dispensed  
with & openings fitted with E. W. steel plates

3" dia. air pipes fitted to each molasses tank, 36" high  
in forward well & 30" high on Bridge deck - fitted with  
wooden plugs.

Sailed  
10/10/41

G. Pratt  
15 Aug. 1941