

Lloyd's Register of Shipping.

-3 JAN 1944

Ship's Name "ESKDALEGATE"

Official No. 161403

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

HATCHWAY (To magazine in Tween Decks) on BRIDGE DECK, STARBOARD SIDE, AFT END.

24" x 24" with 9" coaming and hinged steel W.T. cover.

ADDITIONAL ACCOMMODATION, BRIDGE TWEEN DECKS, AFT END, PORT SIDE.

STEEL COMPANIONWAY on Bridge Deck, Port side, 2" wood door, sill 18".

One ventilator 10" dia., coaming 30" x .32 fitted with wood plug and canvas cover.

SIDE SCUTTLES. ~~Six~~ ^{SEVEN.} side scuttles cut in Bridge Deck sheerstrake, port side,

10" dia. with hinged deadlights.

One side scuttle cut in Bridge End Bulkhead, port side, 16" dia.

with hinged deadlight.

DISCHARGES from W.C., wash basin and shower led overboard above the freeboard
deck.

TONNAGE OPENINGS, BRIDGE END BULKHEAD (I.P. and I.S) closed by bolted plates.

STEEL COMPANIONWAY, POOP DECK, STARBOARD SIDE with 2" solid wood door, sill 18".

George Lullin

Glasgow, 28th December, 1943.

(Wokingham)

J.P.S.
28 JAN 1944