

"GERONTAS"

(Liberty (b))

Built 1943 Bethlehem Fairfield.

-----

This ship is all welded except side shell frames and seams. The bottom has been stiffened, and also local deck stiffening has been arranged.

It is strongly recommended that in view of experience of similar ships the following stiffening should be fitted at an early date.

A girder about 18 ft. from the centreline, P. & S., 12 x .50 with 12 x .80 face to be fitted from frames 134 to 110 and 86 to 54, this girder to be connected to the deck by double riveted angles.

The Owners should be requested to forward proposals.



© 2021

3.54

Lloyd's Register  
Foundation

010615.010612.0199

4291 RAMM & VACCAREN

WEDNESDAY 5 MAR 1954

*Sub<sup>2</sup> approved*

*PA 3*  
*[Signature]*

*[Handwritten scribble]*

(11) (11)

Abfif... B 24 P1 15.28

24710839



© 2021 Lloyd's Register Foundation

CLa  
MAP

Th  
LL  
71

De

11

0  
11

11