



RIVETING		R.V.	CREAKS OF LANDING	SPAC.	TYPE
PLATING					
SEAMS IN SHELL PLATING		WELDED			
FORM IN W.L.		WELDED			
SEAMS IN TANKTOP		WELDED			
DECK		WELDED			
OIL BOTTOM TANK		WELDED			
ANGLES					
FRAME TO SHELL *D - *58		3/4"		130 %	
*B9-STEM AND AFTPEAK		3/4"		95 %	
FRAME TO FLOOR IN ENGINE ROOM		3/8"		110 %	
BEAMS		3/8"		110 %	
BEAMS IN PEAK TANKS		3/8"		95 %	
STEM AND CENTRE GIRDER TO SHELL		WELDED			
STEINPOST TO SHELL		WELDED			
RUDDER		WELDED			
N.W.T. FLOORS:					
ANGLE					
100.65 x 8 F TO TT AND FLOOR		3/8"		110 %	
100.65 x 8 F TO SHELL		3/8"		130 %	
100.65 x 8 F TO FLOOR		3/8"		110 %	
100.65 x 8 F TO SHELL		3/4"		130 %	
100.65 x 8 F TO FLOOR		3/8"		110 %	
8' x 5' x 3/4" F TO SHELL		3/4"		105 %	2 1/2 lbs
8' x 5' x 3/4" F TO FLOOR		3/8"		95 %	2 1/2 lbs
W.T. FLOORS WELDED TO T.T. AND SHELL					
O.T. FLOORS WELDED TO T.T. AND SHELL					

<u>ANCHORS, CHAINS, CABLES: (LETTER H)</u>	
2 - BOWERANCHORS, STOCKLESS, EACH	602 KG
1 - BOWERANCHOR, STOCKLESS,	602 :
355 M. STUD CHAIN CABLE	1/8"
MIN. WEIGHT	6350 KG
1 x 110 M. 2 3/4"	WIRE STEEL ROPE
1 x 135 M. 2 3/4"	WIRE STEEL ROPE
1 x 165 M. 2 1/4"	WIRE STEEL ROPE
1 - STEERMANANCHOR INCLUDING STOCK	250 KG

SCANTLING ETC.

LENGTH P.P. = 47.84 m. = 155'-0"

BREATH MLD = 8.64 m. = 28'-6"

DEPTH TO MAINDK = 3.734 m. = 12'-3"

DEPTH TO RAISED DK = 4.734 m. = 15'-6 3/4"

DRAUGHT ABT.

L x D = 1928

L (B + D) = 6414

YD = 12.85 10.13 TO RAISED DECK.

EN = 7192

FRAMESPACING = 610 mm WITH FREEBOARD

CLASS : LLOYD'S + 100 A1 - SPECIAL

SURVEY STRENGTHENING FOR ICE

NAVIGATION.

LENGTH FOR NUMERALS = (185 + 24)

NOTATION :- ELECTRICALLY WELDED.

NOTATION: ELECTRICALLY WELDED.

1/5 361 "FB79"
1/5 AS FITTED PLAIN
GOTHUBUES 10-3-49
H. JAMES BAKER

CORRECTED	AS	PER	DIR.	FROM	LYOYDS
	DEN	24/7	1946.	NYB #359	
	DEN	29/10	1947	NYB #361	
	DEN	10/8	1948	NYB #362	

750 TONS D.W. MOTOR COASTER			
GOTHENBURG FIRST ENTRY REPORT NO. 16561			
MIDSHIP SECTION.			
(AS BUILT)			
KALMAR VARV.		SCALE 1:25	
DEN G-7-1946		BITAD RV. ÅK.	
		RTIN. NR. 2354	
NVB. NR.	████	361	████
BEST NR.	████	8600	████

"FENJA" ★

midship section (as built)

RECORDS DEPT.,
LONDON

2



© 2020

Lloyd's Register
Foundation

010631-010639-0222