

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "M A R ã O" Official No. -

Port of Registry LISBON

This ship has been under survey at Lisbon, Portugal

on 1st March 1956 and the following alterations to the conditions of assignment of loadlines have now been effected/found:—

BUTTERWORTH FITTINGS

12" diam. openings in Upper Deck, one each for all nine Centre Tanks, and two each for all five P. & S. Wing Tanks, making total of 29.

Coamings 6"x1/2" thk steel, with 1/2" landing ring, welded to deck.

Cover plates steel 1/2" thick, 10-5/8" steel bolts, heads welded to underside of landing rings, brass nuts and oil-tight jointing fitted.

*Lisbon,
2nd April, 1956
J. B. Taylor*

A copy of this Report has been placed on board.

