



# Lloyd's Register of Shipping.

"Broströmia," Packhusplatsen 6,  
Gothenburg, 15th October, 1932.

Enclosure.

Reference

Dear Sirs,

With reference to the request that a Freeboard might be assigned by the Committee of this Society to the

**S.S. "INGRID THORDÉN", Kungsbacka,**

I have to acquaint you that the Freeboards, as set forth below, have been computed under the provisions of the International Load Line Convention, 1930, and to request that you will arrange for the freeboards to be marked on the ship's sides, as shown by diagram on the other side, in order that the marking may be verified by the Society's Surveyors and the fact reported to this Office, with a view to a certificate of freeboard being issued and record thereof made in the Society's Register Book.

I am, Dear Sirs,

Yours faithfully,

*V. Bülou*

**Messrs. Rederi A/B Aranäs,  
Kungsbacka.**

**ORDINARY CARGO ~~XXXX~~ ~~XXXXXXXXXX~~ PASSENGER SHIPS.**

Freeboard amidships from top of deck line, ~~XXXX~~ steel deck.

Tropical Fresh Water . . . . .	267 mm.
Fresh Water . . . . .	387 mm.
Tropical . . . . .	402 mm.
Summer . . . . .	522 mm.
Winter . . . . .	642 mm.
Winter North Atlantic . . . . .	693 mm.

From centre of disc.

255 mm.	above
135 mm.	above
120 mm.	above
120 mm.	below
171 mm.	below

**SHIPS CARRYING TIMBER DECK CARGOES.**


Freeboard amidships from top of deck line, ~~XXXX~~ steel deck.

Tropical Fresh Water Timber . . . . .	146 mm.
Fresh Water Timber . . . . .	268 mm.
Tropical Timber . . . . .	284 mm.
Summer Timber . . . . .	406 mm.
Winter Timber . . . . .	569 mm.
Winter North Atlantic Timber . . . . .	693 mm.

From centre of disc.

376 mm.	above
254 mm.	above
238 mm.	above
116 mm.	above
47 mm.	below
171 mm.	below

Subject to ventilators and air pipes being provided with means of closing and openings in bridge after bulkhead being fitted with Class II closing appliances.



© 2021

010835-010845-0216

Lloyd's Register  
Foundation