

Under
Net
Surv

3m.7.40.

13 AUG 1941

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

VESSEL'S NAME INGRID THORDEN Rpt. Got No. 13082

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

The class is subject to sternframe E.W. 11.31, 1.36 and 1.39 and shell plate (p.s) abreast No. 1 hatch E.W. 6.39 being specially examined at the next dry docking.

The GOTHENBURG Surveyors report the vessel placed in dry dock and the bottom coated.

On account of ice damage and striking quay, 7 shell plates renewed, 38 repaired, 85 frames repaired and minor repairs effected (p & s).

On account of heavy weather, repairs effected to sternframe, rudder and steering gear. ///

30 fathoms of chain cable found strained now removed. The Surveyors recommend 30 fathoms of chain cable be supplied. (1)

Rudder welded in way of second rudder gudgeon (10.40). The Surveyors recommend the rudder be specially examined at the next dry docking. (2)

On account of further heavy weather, a deck plate renewed, 1 repaired (s.s) and a hatch end repaired. ///

The 2nd S.S. No. 2, due 11.40, held and wear and tear repairs to decks, bunkers and minor repairs effected.

Sternframe, as above, examined and now rewelded 10.40.

No welded shell plate abreast No. 1 hatchway could be found.

It is submitted the vessel is worthy to remain as classed with record of survey 10.40 and notation of S.S. No. 2-40, subject to sternframe (E.W. 11.31, 1.36, 1.39 and 10.40) and rudder (2nd gudgeon E.W. 10.40) being specially examined at the next dry docking and to 30 fathoms of chain cable being supplied at the first opportunity, but without other condition.

100A1)
With fbd) Subject, etc.
10.40 Got) Without, etc.
S.S. Got No. 2-40)

was
8-8-41



© 2021
The Finnish vessel

Lloyd's Register
Foundation

010835 - 010845 - 0236

sternfram

and subje

Survey Fee (per Se