

4 JUN 1942

## Lloyd's Register of Shipping.

29778

Ship's Name "D O N J O S E" Manila, P. I. Official No. --

Memorandum ~~of alterations reported since ship was surveyed~~ for assignment of <sup>Timber</sup> Load Lines in October, 1941.

Ship examined afloat at Terminal Dock, Vancouver, B. C., on the 29th and 30th October, 1941, concurrently with survey for deeper loading.

Steel Bulwarks on Upper Deck in fore and aft wells.

48" above steel deck. 7" B.A. top rail.

7" bulb plate stays spaced 3'0" apart.

Steering Gear

Rod and chain gear from Bridge Deck House, led alongside hatch coamings, protected by efficient steel covers to the poop front, the after portion of rods and chains are inside the poop space.

Auxiliary Steering Gear

An efficient hand screw gear on Poop Deck.

D. B. Tanks

A longitudinal centre girder is fitted in the D. B. Tanks for the midship half length.

Eyeplates, Lashings and Fittings for Uprights

None fitted.

The vessel has a Poop Bridge and Forecastle.

*J. H. M.*

SURVEYOR TO LLOYD'S REGISTER.

Vancouver, B.C.

FEE \$ 25.00

Expenses 1.00



© 2021

Lloyd's Register  
Foundation

010858-010865-0349