

010905-010912-0226

S/S "AMARANTE" ex "Wurtenberg"

This vessel was built by Messrs. Bremer Vulkan Vegesack in 1914.

The classification with this Society is contemplated and a plan of the boilers has been forwarded for consideration.

The scantlings of the boilers as shewn on the plan meet the requirements of the Rules, in force at the time the boilers were constructed, for the original working pressure of 14 Kgs. per sq. cm., with the exception of the thickness of the furnace plates, which, owing to the low tensile strength of the material employed, is slightly less than required by the Rules.

IT IS SUBMITTED that provided the machinery be opened out and examined and found in good condition, the sizes of the shafting be such as could be accepted, the boilers be examined throughout, their scantlings be found in accordance with the plan, the furnaces be specially examined and found to shew no sign of strain, and the pumping arrangements be in accordance with the requirements of the Rules, the machinery of this vessel might be accepted for the original working pressure of 14 Kg. per sq. cm. and a notation of LMC (with date) without the distinguishing mark ~~to~~, be assigned.

Particulars of the main engines & sizes of the shafting together with a plan of the pumping arrangements should be forwarded for consideration. Return 1 plan.

his
31/3

L 17/4/25

© 2021 Lloyd's Register
J.R.R. A.M.B. 9.4.25