

S.S.264 MIDSHIP SECTION.

DIMENSIONS 430'0" B.P. x 56'7" B.M.D. x 33'5" M.D. TO UPPER DECK.

To CLASS 100 A1 LLOYDS

SCALE 1/2" = 1 FOOT.

LLOYDS NUMERALS
BREADTH MLD. 56.75
DEPTH MLD. 33.50
TRANSVERSE No. 30.25
LENGTH B.P. 430
LONGITUDINAL No. 38807.50
POOP, BRIDGE & FOLL. 1080.00
HOUSES 375.00
EQUIPMENT No. 40262.50
L 12.83

EQUIPMENT		
2 BOWER ANCHORS	65 CWTs.	STOCKLESS
1 " "	642 "	"
1 STREAM "	19 "	EX. STOCK.
270 FATHOMS	2 3/8	STUD CHAIN CABLE
30 " "	5	STEEL WIRE
120 " "	5 1/4	"
2 @ 90 FATHOMS	2 3/8	STEEL WIRE
2 @ 90 FATHOMS	3 1/4	STEEL WIRE.



Hand 264

Indship Section

(Ashuel)

Is Tacito

Wm. 48591



© 2020

Lloyd's Register
Foundation

010913-010923-0197