

Twin Sc. m.s. "BAHR NAGASH", No. 38402 in Supplement.

Classification Contemplated.

Lloyd's List 23.12.47.

BAHR NAGASH.—Port Sudan, Dec. 22.—
Ethiopian motor vessel Bahr Nagash,
(Grangemouth and) Suez for Massowah,
in ballast, has put in here leaking in
vicinity of port A frame. Now trimming
ship to facilitate preliminary inspection,
subsequently slipping or repairing afloat
under surveyor's recommendations. Leak
is at present under control.

" 31.12.47

BAHR NAGASH.—Port Sudan, Dec. 30.—
Motor vessel Bahr Nagash has effected
temporary repairs; certificate of sea-
worthiness granted and vessel has
proceeded. (See issue of Dec. 23.)

" 14.1.48

BAHR NAGASH.—Port Sudan, Jan. 5.
—Motor vessel Bahr Nagash was sur-
veyed here on Dec. 27 and 28 in respect
of a leak in the vicinity of strut sup-
porting forward end of port stern frame.
Temporary repairs to holed and buckled
plate were effected by means of a
cement box, and a certificate of sea-
worthiness was issued. (See issues of
Dec. 23 and 31.)

" 20.1.48

BAHR NAGASH.—Massowah, Jan. 13.—
Motor vessel Bahr Nagash was surveyed
here on Jan. 2 and 9 to ascertain damage
stated to have been sustained through
heavy weather while on voyage from the
United Kingdom (Grangemouth) to this
port. Broken welding of two sounding
pipes from upper deck through No. 1
hold was renewed, two loose angle irons
on fore and aft centre girder were re-
riveted and rewelded, broken welding on
port and starboard girders renewed, butt
straps fitted to fractured bulkhead and
sprung angle bar of wheelhouse bulk-
head rewelded to surveyor's satisfaction.
A certificate of seaworthiness was issued.
(See issue of Jan. 14.)

*See copies for Surveyor Rpts
supplied by Ende Shermors*



© 2021

Lloyd's Register
Foundation

010961-010969-0202