

Steel Quadruple Screw Turbine Steamer No. 1 (High Walker Yard)
proposed to be built by Messrs. Vickers-Armstrongs, Ltd., with
a view to class 100A1 "With Freeboard".

Owners:- Messrs. Furness Withy & Co. Ltd.

Rule Dimensions:- 552.96' x 76.5' x 59.75' to "A" deck
51.5' to "B" deck.
43.25' to "C" deck.

Scantling Nos: (Equivalent Ship):- 22162 and 64464

Proportions:- Length = 9.25 depths to "A" deck.

Plans of midship section and framing profile
submitted, in duplicate, by the Barrow Surveyors.

This vessel, which is similar to the M.S. "BERMUDA"
but with increased dimensions, is proposed to be fitted with
Turbo-Electric machinery.

As requested by the Builders, approval of the
scantlings of the shell and double bottom structure was
indicated to them on the 11th instant.

It is submitted that provided

Compliance

the vessel will be eligible to be classed 100A1 with a freeboard
corresponding to an extreme draught of 26'-6" for all seasons.

The high elastic steel proposed to be used in the
upper parts of the vessel's structure should be in accordance
with Section 7 of the Rules for Quality and Testing of
Materials.

W. J.

25. 4. 30.



© 2021

Lloyd's Register
Foundation

011057 - 011061 - 0126