

**(LLOYD'S REGISTER.)****VESSELS OF 100 TONS AND UPWARDS.**

*These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.*

Signal Letters (if any).....

Official Number.	Name of Ship.	No., Date, and Port of Registry.
168062	"NASPRITE"	15 in 1941 London.

No., Date, and Port of previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw	Glasgow	1940	Blythswood Shipbuilding Co. Ltd., Glasgow.

Number of Decks	...	...	One	Length from fore part of stem, to the aft side of the head of the stern post	...	...	...	...	Feet.	Tenths.
Number of Masts	...	...	One	Main breadth to outside of plank	...	...	...	...	204	5.0
Rigged	...	...	Not	Depth in hold from tonnage deck to ceiling amidships	...	...	...	...	33	2.0
Stem	...	...	Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	...	...	...	...	13	5.0
Stern	...	...	Cruiser	Depth from top of deck at side amidships to bottom of keel	...	...	...	...	13	6.35
Build	...	...	Clinker	Round of beam	...	...	...	...	49	6.0
Framework and description of vessel	...	...	Steel cargo	Length of engine room, if any	...	...	...	...		0.0
Number of Bulkheads	...	...	Thirteen							

*Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.*

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Inverted cylinder Triple expansion	Engines.  British	Engines.  1940	Engines. David Rowan & Co. Ltd., Glasgow.	Three 15" 25½"	30"	/	162 / 750
No. of Shafts.	Particulars of Boilers. Horizontal Return Tube Description ..... Single ended.	Boilers.	Boilers.	Boilers.	41"			10 knots
One	Number ..... Two Iron or Steel ..... Steel Loaded Pressure ..... 190 lbs.	British	1940					

Number of water ballast tanks, and their capacity in tons:— Six = 327.6 tons.



# PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ... ..	642.33	On account of space required for propelling power	363.51
Space or spaces between Decks ... ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	193.78
Turret or Trunk ... ..	47.87		
Forecastle ... ..	106.77	These spaces are <sup>in</sup> the following, viz. :—	
Bridge space ... ..	128.15	Poop and Bridge	
Poop <del>or Break</del> ... ..	11.08	(Number of Seamen or Apprentices for whom accommodation is certified.....25.....).	
Side Houses ... ..		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Deck Houses ... ..	28.55	Master's Accommodation 6.77	
Chart House ... ..		Chart Space 4.64	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ... ..		Cubic Metres. Wireless Space 4.55	101.47
Excess of Hatchways ... ..		Boatswain's Store 10.00	
		Water Ballast Spaces 61.29	
Gross Tonnage ... ..	964.75	Ballast Pump Spaces 14.22	
Deductions, as per contra ... ..	658.76	Total ... ..	658.76
Register Tonnage ... ..	305.99		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is.....179.17.....tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is.....85.48.....tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	The Secretary of the Admiralty,
Name, Residence, and Description of Managing Owner if there are more owners than one.	Whitehall, S.W.1 designated
His Majesty represented by the Commissioners for executing the Office of Lord High Admiral of the United Kingdom, London.	Managing Owner under Order in Council 22nd March, 1911.
Shares. Sixty four.	
Dated 29th January, 1941.	