

20 OCT 1947

Rpt. C. 11 (Contd.)

Glasgow Rm 72206

Index No.

Lloyd's Register of Shipping.

Ship's Name "ADULIS" (ex L.C.T. No. 835).

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The sluice valves on the overboard discharges from the W.C.'s and washplaces in the fore-castle tween decks are now controlled from an accessible position on the fore-castle deck, the controls are fitted with indicators. ✓

The overboard discharges from the washbasins, showers and galley sink situated in the poop tween decks, have each been fitted with two automatic non-return valves, the upper valve is so situated that it is always accessible for examination under service conditions. ✓

The valves in the W.C. pans situated in the poop tween decks are automatic non-return valves and have a metal seating. ✓

Lifelines are fitted all fore and aft on the freeboard deck, extending from the poop front to the fore-castle. ✓

2 in No., 4½" dia. gooseneck ventilators fitted on poop deck, to poop tween decks, of efficient construction, each 32" high. ✓

MLD

hond.
20 OCT 1947

James M. Sanders

GLASGOW, 23rd September, 1947.

