

LLOYDS STAMP
16-6-55

DIMENSIONS:-

LENGTH B.P. - 123'-0"
BREADTH MLD. 17'-3"
DEPTH MLD. 8'-0"

SELF PROPELLED ALL WELDED CANAL BARGE

CLASSIFICATION:- LLOYDS + A.I. BARGE CARRYING PETROLEUM
IN BULK FOR SERVICE ON THE
RIVER HUMBER, TRENT CANALS &
AIRE & CALDER CANALS
ALL WELDED CONSTRUCTION.
STIFFENED FOR LYING AGROUND.

EQUIPMENT:-

1- BOWER ANCHOR - 4½ CWT. STOCKLESS
60 FATHOMS - ¾" CHAIN CABLE
25 " - 2" WIRE TOWLINE
2- 15 " - 6" FIBRE HAWSER
2- 15 " - 4" " "
10 " - 1½" CHAIN HEADFAST (NOT FITTED)

NUMERALS

L = 123'-0"
B = 17'-25"
d = 7'-05"
D = 8'-00"

$L \times (B+d) + .85 L \times (D-d) = 3066$
 $RAD = .85 \times (30.58 \times 4.25) = 110$
 $TRUNK = .85 \times (58 \times 2.075) = 142$
NUMERAL = 3340.

LLOYDS MINIMUM TEST HEAD 2'-0"

OWNERS REQUIREMENT - 4'-0" TEST HEAD

CARGO TANKS TESTED TO A HEAD OF 4'-0"
ABOVE TOP OF TRUNK

PEAK TANKS TESTED TO A HEAD
OF 3'-0" ABOVE CROWN OF TANK

TESTED TO 4'-0" PER OWNERS SPEC^N

RAISED QUARTER DECK 4'-3" ABOVE MAIN DECK

SECTION THRO' ENG. ROOM.

SECTION THRO' CARGO TANKS.

SECTION THRO FORE PEAK
WATER BALLAST TANK.

DETAIL OF BRACKETS (MARKED 'B')
TO TRANSVERSES

DETAIL OF DRAIN SLOTS
AT LONGITUDINALS

DETAIL OF STIFFENERS (MARKED 'S')
TO TRANSVERSES

STEM BAR 3" DIA ROUND
STERN POST 5" x 3"

APPROVED BY OWNERS 2/6/55
APPROVED BY LLOYDS 16-6-55

RICHARD DUNSTON LTD.
SHIPBUILDERS,
THORNE, YORKSHIRE.

DRAWN BY J.H.S.	DATE 20-5-55	This Drawing and the Information it contains are the Property of RICHARD DUNSTON LTD. It is not to be Traced, Copied or Published without their Written Consent, nor is the Information thereon to be misused in any way.	
TRACED BY S.Z.H.	DATE 19-6-56		
CHECKED BY	DATE		
REVISIONS			
No.	DATE	PARTICULARS	
A	16-6-55	APPROVED BY LLOYDS	
YARD No T. 914/16		DRG. No. 55674/A	
TITLE:- MIDSHIP SECTION			
SCALE:- 1/2" TO ONE FOOT			

© 2021 Lloyd's Register Foundation

"Esso SALTEND" ★


Richard Dunstan Ltd.

Yard No 916.

Hull. H.E. Report No. 62532.

MIDSHIP SECTION (As fitted)

RECORDS DEPT..
LONDON.



© 2021

Lloyd's Register
Foundation
011273-011274-0158



0158



© 2021

Lloyd's Register
Foundation