

Received London  
22. MAR. 1963

Ship's Name **SS/MS Barge "PEGASUS 3"** Gross tons **100**

Is there a rpt. 9? **No** Port **Lagos** Rpt. No. **3485**

No. of visits **6** First date **10 - 2 - 63** Last date **12 - 3 - 63**

Interim Cert. issued & copy herewith? **Yes** Damage rpt. issued & copy herewith? **No** Last rpt. (H.Q. only) **3205**

Date of completing rpt. **15 - 3 - 63** Surveyed at, if different from Port above

Surveyed afloat and/or in D.D. **Both** Last date of examination in D.D.

Has a Load Line Survey been held? **No** Freeboard Marks verified

State which additional Rpt. 8 is attached: (Cont); (PS); (DR); (EQ); (Rig)

Survey fees DS **£10 - 0 - 0.** Damage fee Reqs **£20 - 0 - 0.** Expenses **£3 - 0 - 0.**

Part S.A. fee **£2 - 6 - 8.**

I have surveyed the above ship in accordance with the Rules for **Annual Survey & Drydocking.**

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.

Repairs for damage, the causes of which were not stated:

Found:

Keel plates No.1 & 2 from aft set up in way of aft buoyancy space and No.2 Port & Starboard tanks. Starboard forward corner plate set in, in way of forward buoyancy space.

Starboard sheerstrake No.1 plate from forward indented and deck plate in way buckled locally.

Starboard sheerstrake 3rd plate from forward indented.

Now Done:

Keel plates No.1 & 2 from aft renewed. Aft buoyancy space and No.2 Port & Starboard tanks satisfactorily pressure tested on completion.

P.T.O.

I recommend that this ship remain as classed with/without fresh record of dry docking **2/63.**

These conditions of class are recommended to retained, imposed, amended or deleted, particulars to be stated above and on the interim certificate.)

Date of Committee: **THURSDAY 11 APR 1963**

Minute **D6 2. 63**

*H. Pollock*  
H. Pollock  
Surveyor to Lloyd's Register of Shipping



Lloyd's Register  
Foundation

011280-011293-0309 1/2

ALSO FOR

SPL FOR

TRO

SRL

POSTING

HEADER

CERT

28 MAR 1963

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

Starboard forward corner plate renewed. Forward buoyancy space satisfactorily pressure tested on completion. Starboard sheerstrake No.1 & 3 plates from forward cropped and part renewed.

On completion the No.1 Starboard & No.2 Starboard tanks were satisfactorily pressure tested.

PARTICULARS OF DEFECTS, REPAIRS, ALTERATIONS, ETC. The reason for repairs must be stated as repairs on account of damage, the alleged cause of which must be given, should be detailed separately from wear and tear repairs and, besides being detailed above, should be noted in the following summary. State what action has been taken regarding items which are subjects of class or in SRL Appendix, whether outstanding or new. Any alterations existing particulars in the Register Book should also be reported above.

SUMMARY OF DAMAGE REPAIRS	SHELL PLATES	FRAMES	DECK PLATES	BEAMS	OTHER ITEMS
Renewed	5				
Removed and faired or replaced	'				
Faired or repaired in place					

Rpt. 8 (P.S.) TANKER

Ship's Name ~~SS/MS~~ Barge "PEGASUS 3"

S.S. ( ) Due

Port Lagos

Rpt. No. 3485

Examined & condition		Examined & condition	
In dry dock from	10 - 2 - 63	* Hatchways	Good
" " " to	19 - 2 - 63	* Ventilators	Good
Shell plating	Good	* Air & sounding pipes	Good
Sternframe	-	Doublers under sounding pipes	Not Examined
Rudder	-	Steering arrangements (main)	None
Was rudder lifted?	-	" " (aux)	None
Plating, etc. in way of shell openings	None	Windlass	None
Side scuttles & deadlights	None	Masts & rigging	None
Overbd. scuppers & discharges	None	Hand pumps & suctions	Not Examined
Hold	None	W.T. doors	None
F.P. spaces	None	Bulwarks, freeing ports, etc.	None
Chain locker	None	Summer freeboard as verified	-
A.P. spaces	None	<u>EQUIPMENT:</u>	
Engine space	None	Equipment letter	
Boiler space	None	Anchors: No. on board	None
Under E. & B.	None	Cables {	State if ranged -
Coal bunker	None		Length on board -
Tunnel & well	None		Mean dias. range from - to -
Cement, asphalt, etc., on btm. shell	Not Examined		Rule length - Dia. -
Weather decks	Good	Mooring ropes	-
* Casings	Good	Other items:	
* Deckhouses	Good		
* Superstructures	Good		
* Skylights	-		
Companionways	None		

EXAMINED & CONDITION		TANKS	TESTED & CONDITION	
PORT	STARBOARD		PORT	STARBOARD
		F.P. Tank		
		A.P. Tank		
		Deep Tank No. 1		
		" " No. 2		

other tanks see overleaf

these items to include their closing appliances

are a part Special Survey and, say, dry docking Survey are held at the same time, the items for SS should be marked "For SS".

