

(2) the freeing ports being fitted with a horizontal rail or bar in accordance with Rule 35(c) of Statutory Rules and

011294-011303-0106

5m.5.32.

FREEBOARD REPORT on the Tanker "Silfield."

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to

- (i) the companionway on the forecastle deck being fitted with a steel door which can be manipulated from both sides, the door sill being at least 24" in height.
- (ii) the freeing ports being fitted with a horizontal rail or bar in accordance with Rule 35 (c) of Statutory Rules and Orders 1932. N° 96.
- (iii) the exposed machinery casing on Poop deck being fitted with a steel door in accordance with Rule 97 of Statutory Rules and Orders. 1932. N° 96.

In making the computation it has been assumed that the Bridge forward and after end bulkheads extend from side to side of ship (i.e. that the space between the trunk top and bridge deck is enclosed) but the surveyors should confirm this.

Convention. Tanker.

Ans 25/3/32
Rat & Humphrey's Ed



© 2021

Lloyd's Register
Foundation

The
beam
report-
e full
vessel
rate.

10 1/2
6 1/2
X 3 3/4
4
X 3 1/2
X 3 3/4
11 3/4

3 1/2
8 1/4