

8 JAN 1951

## Lloyd's Register of Shipping.

Ship's Name *ARGOBEC*Official No. *174791*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in *JUNE '43, MARCH '46 & NOVEMBER '47*

*No 3 hatch has been found combined with crossbeam hatch. Particulars are now as follows:*

*Decks of Hatch. No 3 cargo hatch*

*Dimensions 25'-3" x 20'-0"*

*Coamings Height above deck 30"*

*Sides .44*

*Thickness Ends .44*

*Stiffener 1 7/8 x 3 x .38*

*Brackets 40 - 3" fl.*

*Hatchbeam Number 4*

*Spacing 5' - 10" MAX.*

*Scantlings 0.4 5 x 3 x .882*

*.34 18 1/2"*

*Bearing Lugs 3"*

*Hatchcover Material Pine*

*Thickness 3"*

*How fitted Long.*

*Bearing Surfaces 3 1/2" MIN.*

*Spacing of cleats MAX 24"*

*Number of tarpaulins 3.*

*Both wing beam hatches have been found removed and openings in deck plated over.*

*A copy of this C.11 (Cont.) report embodying the above alterations has been forwarded to the vessel*

*W B Thulds*

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

ROTTERDAM DECEMBER 1950.

*Noted*  
16 JAN 1951



© 2021

Lloyd's Register  
Foundation