

Lloyd's Register of Shipping.

SHIP OR ENGINE FORGINGS OR CASTINGS.

I have to report that the Forgings or Castings, as herein described, manufactured by GLOBE ENGINEERING WORKS LTD., of CAPE TOWN,

for the Engines No. - being mounted by -
of M. V. "MASHONA" of CAPE TOWN

have been inspected by me as set forth below, and found to be, so far as can be seen, sound and free from defects. These have been despatched to fitted and placed on board as spare

ITEM	SCREWSHAFT	INTERIM SHAFT	SPARE SCREWSHAFT
Identification No.	B.C. Ctn. No. 5 J.vL 2-2-50.	B.C. Ctn. No. 6 J.vL 2-2-50	B.C. Ctn. No. 7. J.vL 2-2-50
Surveyor's Initials.	J.vL	J.vL	J.vL
Materials.	O.H. Ingot Steel	O.H. Ingot steel	O.H. Ingot Steel
How made.	Forged	Forged	Forged
Heat treated.	Yes	Yes	Yes
Dimensions.	D 5 1/2" L 10' 6 5/8"	D 5" L 10' 10"	D 5 1/2" L 10' 6 5/8"
Weight.	800 lbs	735 lbs	800 lbs
Progress on Insp.	Black rough machined and finished	Black rough machined and finished	Black rough machined and finished
Yield tons per sq. 1"	17.7.	17.6	17.5
Ult. tons per sq. 1"	32.5	32.3	32.0
Elong. % on 2"	34.5%	36%	34.5%
Reduc. of Area %	56%	58%	54%
Cold Bend.	180° without fracture radius 1/4"	180° without fracture radius 1/4"	Without fracture radius 1/4"
Brinell.	-	-	-
Izod.	-	-	-
Final date.	2-2-50	2-2-50	2-2-50

Date of approval of chemical analysis, physical properties and heat treatment in the case of special steels for reduction gearing forgings.

Other tests: -

Fee: Please see Report 8.

Signature

Expenses:

*Delete where not applicable.

Date 8-3-51.