

21 OCT 1963

Ship's Name ~~SS/MX~~ "OAK HILL" 7139 Gross tons  
Is there a rpt. 9? Yes. Port Piraeus Rpt. No. 10563  
No. of visits 2 First date 17.9.63 Last date 24.9.63  
Interim Cert. issued & copy herewith? Yes. Damage rpt. issued & copy herewith? No. Last rpt. (H.Q. only)  
Date of completing rpt. 10.10.63 Surveyed at, if different from Port above Syra  
Surveyed afloat and/or in D.D. Both Last date of examination in D.D. 24.9.63  
Has a Load Line Survey been held? Yes/ Freeboard Marks verified Yes.

State which additional Rpt. 8 is attached: ~~(XXX)~~ (PS); ~~(XXX)(XXX)~~ (XX)

Survey fees Damage fee Expenses £1. 0. 0  
DS £20. 0. 0

S.A. fee -

I have surveyed the above ship in accordance with the Rules for Docking Survey.

The items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.  
Minor wear and tear repairs effected.

Conditions of class

Indented shell plates H14,15, J14(p.s.), J16 etc.,(s.s.) from aft, indented stem and stem plating etc., (p. & s.) indented wing plates aft bulkhead (p.s.). Oil fuel tank No.4 hold and indented and set up bottom shell plating etc., (p & s) in way of Nos.1/8 double bottom tanks all examined this time, but no repairs carried out, still remain efficient, it is recommended however that all above items be examined and dealt with at the Special Survey.

Annual Load Line Repairs

Number of hatch covers fitted with coxes ends.  
Forward port engine room skylight doubled in way of wastage.  
2 air pipe goose necks renewed (s.s.).  
All above repairs examined on completion and all found satisfactory.

I recommend that this ship remain as classed with ~~without~~ fresh record of dry docking DS 9,63, subject to indented shell plates H14 and H15, J14 (p.s.), J16 etc., (s.s.) all from aft, indented stem and stem plating etc.,(p & s), indented wing plates aft bulkhead (p.s.) oil fuel tank No.4 hold and indented and set up bottom shell plating etc. (p & s) in way of Nos.1/8 double bottom tanks being examined and dealt with at the Special Survey.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Date of Committee

FRIDAY 22 NOV 1963

Minute

DS 9. 63 subject (h. fm)  
MBS 9. 63

Surveyor to Lloyd's Register of Shipping

Lloyd's Register  
Foundation

011485-011492-0018 1/2

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

date of the next Special Survey. Where repairs have been effected or it is considered that re-examination or repairs should be made before that date the circumstances and

The condition of any item is to be described as "good" only when it has been examined, found or placed in good condition and is considered to be acceptable until the due

Ship's Name SS ~~MS~~ "OAK HILL"

S.S. ( ) Due

Port Piraeus

Rpt. No. 10563

	<u>Examined &amp; condition</u>		<u>Examined &amp; condition</u>
In dry dock from	24.9.63	* Air & sounding pipes	Good (Above dk).
" " " to	25.9.63	Doublers under " "	N.E.
Shell plating	Good.	Steering arrangements (main)	Good.
Sternframe	Good.	" " (aux)	Good.
Rudder	Good.	Windlass	Good.
Was rudder lifted?	No.	Masts & rigging	Good. (From dk)
Plating, etc. in way of shell openings	Good.	Hand pumps & suction	N.E.
Side scuttles & deadlights	N.E.	W.T. doors	N.E.
Overbd. scuppers & discharges	Good.	Bulwarks, freeing ports, etc.	Good.
F.P. spaces	N.E.		
Chain locker	N.E.	Summer freeboard as verified	10' 6½"
A.P. spaces	N.E.		
Engine space	N.E.		
Boiler space	N.E.	<u>EQUIPMENT:</u>	
Under E. & B.	N.E.	Equipment letter	
Coal bunker	None.	Fee ltr., if diff. from eqpt. ltr.	
Tunnel & well	N.E.	Anchors: No. on board	
Cement, asphalt, etc., on btm. shell	N.E.		
Weather decks	Good.	Cables {	State if ranged No.
* Casings	Good.		Length on board
* Deckhouses	Good.		Mean dias. range from to
* Superstructures	Good.		Rule length Dia.
* Skylights	Good.	Mooring ropes	Good.
* Companionways	Good.		
* Hatchways	Good.		
* Ventilators	Good.		
Other items:			

\* These items to include their closing appliances

Where a part Special Survey and, say, Dry Docking Survey are held at the same time, the items for SS should be marked "For SS"



© 2021

 Lloyd's Register of Shipping  
 Surveyor to Lloyd's Register of Shipping  
 Foundation