

B. C. SHIP

56554
20 MAY 1950

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "TEN HENSHAW".

Official No. 163394.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Small hatch on forecastle deck to forecastle space below 18" diameter
coaming 15" x .30" with steel hinged lid secured by toggles and wing nuts.

Skylight on poop deck to galley below strongly constructed with steel
coaming 30" high and hinged steel flaps.

Side scuttles are fitted in poop side plating to accommodation in poop
space, scuttles of substantial construction with hinged deadlights.

3" air pipe in forecastle space to fore peak tank G.N. pipe 36" high with
opening 30" above deck.

2 @ 3" diameter pipe scuppers at after end of upper deck scuppers led through
shell below deck.

R. S. Piddington
SURVEYOR TO LLOYD'S REGISTER
OF SHIPPING, HULL.

15.5.50.

Noted
[Signature]
22 MAY 1950

