

WINTER HILL

with the rules found satisfactory.
Settling tanks in accordance with the enclosed approved plan fitted in the tween
 decks & efficiently anchored to the structure of the vessel. gutterway bars & scupper
 fitted as shown on plan. Tanks tested & found satisfactory.
 Air pipes to settling tanks, deep tank & No 7 & 8 double bottom tanks fitted with
 gauge.

The remaining requirements of Section 42 of the British Corporation rules complied
 with where applicable.

Alterations - Tunnel & watertight door in cross bunker forward of boiler
 room taken out of vessel and bulkheads in way of same efficiently stiffened
 to conform with the remainder of the bulkhead.

No 86 bulkhead openings in this bulkhead closed by welded plates & bulkhead
 made watertight & suction & sounding pipes fitted in this compartment but
 the stiffening of this bulkhead has been deferred until the next special survey
 in agreement with. London letter dated 20/10/50 to the Owners a copy of which is
 attached.

One shoot taken out of vessel & hole in ships side efficiently closed by welded spigot patch.
Coal Hatch No 5 in way of boiler casing. coamings removed & opening in deck closed
 by .60 plate rivetted & welded.

Watertight door fitted to shaft tunnel controlled from upper deck & tested on completion.

It is understood that the Owners intend to carry cargo in the space

originally designed as a cross bunker.

Spare lower anchor & 45 fathoms of cable supplied. marks verified with certificate. Particulars of
 testing noted below.

When Anchors or Cables are supplied, the particulars are to be reported in the following form :-

ANCHORS.

Number of Certificate.	Anchor.	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST PER CERTIFICATE.				WEIGHT REQUIRED BY RULE.			Description of Anchor.	Makers.	Where and when tested and Superintendent.
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons	Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.			
4955	1st Bower																
	2nd "														HINGLEY CHALLENGE	N. HINGLEY	N. 10/8/50 HIBBS
	3rd "	68	0	0	STOCKLESS			52	12	2	0				Y SONS LTD		
	Collection Weights																
	CAST STEEL HEAD:-														W/INC PINS 43.0.25 - CERT N° 1175 TESTED 23/9/49 AEG.		
	Kedge																

* When a bower anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bower.

CHAIN CABLES.

Number of Certificate.	Length and size supplied.		Test per Certificate.		WEIGHT OF CHAIN CABLE.		Length and size per rule.		Description.	Makers of Cables.	Where and when tested and Superintendent.
	Length.	Diam.	Statutory.	Breaking.	Supplied.	Per Rule.	Length.	Diam.			
	Fathoms.	Inch.	Tons.	Tons.	Cwts. qrs. lbs.	Cwts. qrs. lbs.	Fathoms.	Inch.			
82420	30	2 5/16	96 5/20	134 15/20	82.2.24		25 1/2	2 5/16	STUDLINK	N HINGLEY & SONS LTD	C.H. 3/10/50 PHILLIPS
79999	15 1/2	2 5/16	"	"	40.0.0		"	"	"	"	C.H. 15/9/49 MURPHY.
Iron Stream Chain or Steel Wire											

Note:- plans of settling tank & additional stiffening fitted to deep tank.
 also copy of endorsement of January 5th 1950 are forwarded herewith.

Decks, casings, holds & tween decks, hatchways vents, mudlars & steering gear
 & general equipment examined & found in order.

[Signature]



© 2021

Lloyd's Register Foundation