



≡ GENERAL NOTES ≡

1. STEEL FRAMES TO COMPLY WITH LLOYD'S REGISTER OF SHIPPING & AMERICAN BUREAU OF SHIPPING REQUIREMENTS & TEST
2. MOLD LIFT TO FURNISH PATTERN SHOP WITH ALL NECESSARY TEMPLATES
3. ALL RIVET HOLES TO BE LAID OFF & DRILLED BY HAND
4. ALL TAPERS IN VERTICAL WEBS TO BE ON AFT SIDE
5. ALL TAPERS IN HORIZONTAL WEBS TO BE ON LOWER SIDE
6. FLOORS TO BE EFFICIENTLY RIVETED TO AFTWARD SHIP WEBS
7. RIVETING TO BE IN ACCORDANCE WITH CLASSIFICATION SOCIETIES RULES

The photo writing must be done with an approved chemical and the application of an approved solvent. THE PHOTOGRAPHIC UNIT OF THE FBI AND THE FBI LABORATORY OF NEW YORK AND WASHINGTON FIELD OFFICE MUST BE CONTACTED.

Surgeon City

DUPLICATE FOR H-4333 CHARGE-ED-4333

CHARGE-ED-4332 JOB No. 121

H-4332-12-1 53
BETHLEHEM SHIPBUILDING CORP., LTD
SPARROWS POINT, MD

STERN FRAME

SCALE $\frac{1}{2} = 1'-0"$ As Noted DATE MAY 3RD '32

DRAWN BY R. STEWART APPROVED

TRACED BY DL APPROVED

CHECKED BY RA APPROVED

RC

Lloyd's Register
Foundation