

Lloyd's Register of Shipping.

Ship's Name S.S. "DORVAL PARK" TAKE CANIM Official No. 175389

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in May, 1944.

ALTERATIONS - NOW DONE:-

Removal of D.E.M.S. Accommodation & Fittings also "A" Frame for Paravane Gear

Port Side - Accommodation in No. 5 'Tween deck forward of No. 19 bulkhead
now removed.

Fore and after steel bulkhead forming side of accommodation
extending from 19 to 40 bulkhead removed and No. 19 bulkhead extended
to ship's side and efficiently stiffened with 4 vertical angle stiffeners.

Upper deck 3 - 6", 1 - 24", 1 - 12" ventilators also air vent
to toilet and 1 extension spindle removed.

'Tween deck space 9 sidelights, also 2 scuppers and 1 waste pipe
under second deck removed.


Star Side - Steel bulkhead moved aft 3 frame spaces from frame 33 to 30 and
efficiently electrically welded.

2 sidelights in 'tween deck space and 1 - 24" escape hatch on
upper deck removed and aperture closed with welded steel plate.

All ventilator openings in decks, also sidelight and scupper
openings in shell efficiently closed with electrically welded spigot
steel plates.

Bulkheads, decks and shell plating in way of alterations all
satisfactorily hose tested on completion.

"A" Frame for Paravane gear now removed and holes in shell plates
efficiently closed with welded plates.



SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

Vancouver, B. C.

15th February, 1946.

Noted
J.W.
27/3/46

No copy of this Report has been placed on board the ship, being of
Canadian Registry.