

5c.10.40.

Barclay Curle & Co.Ltd., Glasgow.

Yard No.689

ent to Chief Surveyors.....

Received from Chief Surveyors.....

VESSEL'S NAME m.v."PHILIPS WOUWERMAN" (ex "Empire Report Gls. No. 66732
Courage").

For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR.

(In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

ature of Survey. First Entry When due

This is a sister vessel, with modifications, to the "EMPIRE HIGHWAY"

The scantlings have been approved for a draught of 18" in excess of that corresponding to the freeboard which could be assigned as a C.S.S. vessel.

The Tank top plating has been increased in thickness under the hatchways in lieu of ceiling.

100AL "With freeboard" "Carrying cargo oil, FP above 150°F, in deep tank abaft machy.space."

2 Dks

Cell DB 301' 1179t, DTa 30' 1254t, tank in way of tunnel 433t, wing tanks fwd 238t, FPT 139t, APT 93t.

FK, 8BH (Coll to W dk, 7 to 2nd dk) 6 divisional W.T.BHs in 'tween dks, pt. Cem., Lloyd's A & CP.

F 36'

O.L. 431.3'

E.S.D.

at

2"

DELETED SEE RIR.
RP No. 9093

The class is assigned and maintained upon the understanding that the equipment of anchors will be made to accord with the requirements of the Rules when the present state of emergency has passed, that hatch covers at the 2nd deck and cargo battens will be fitted at the first available opportunity and that sparring be fitted to the after bulkhead of the deep tank abaft the machinery space before loading cargo oil.


Insert in S.R.L. (A bower anchor to be supplied).

Hatch covers at the 2nd deck and cargo battens to be fitted at the first opportunity.
Sparring to be fitted to after bulkhead of deep tank abaft machinery space before loading cargo oil.

*Stafes
Jury*

J.C.D.
.....
12.3.43.

B.A.D.



© 2021

Lloyd's Register
Foundation

011877-011883-0056