

5 - MAY 1947

Rpt. C (Contd.)

Index No. 16613

SAN ROBERTO Lloyd's Register of Shipping.
ex "PACIFIC BREEZE"

Ship's Name ex "ASHBURTON"

Official No. 180963

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1946.

Access hatches fitted on main and shelter decks leading to Nos. 1, 2, 4 & 5 hold spaces.


Size of hatches. No. 1, shelter deck. 27" x 24" x 32" in height. 3/8" thick plate, having hinged steel cover and suitable fastenings. ✓

Nos. 2, 4 & 5, shelter deck. 28 1/2" x 27" x 32" in height. 3/8" plate; having 3" wood covers, cleats, battens and tarpaulins. ✓

No. 1, main deck. 27" x 23 1/2" x 9 1/2" in height, 3/8" plate, having 3" wood covers, cleats, battens and tarpaulins. ✓

Nos. 2, 4 & 5, main deck. 28 1/2" x 27" x 9 1/2" in height. 3/8" plate; having 3" wood covers, cleats, battens and tarpaulins. ✓

J. Brooke Smith



22-4-47.

M.L.D.

Noted
5-5-47.
G.J.



© 2021

Lloyd's Register
Foundation