

Rpt. 8

Port Sourabaya

No. 6166.

Date of writing Report 9 - 12 - '57.

When handed in at Local Office

Received London 17 DEC 1957

Survey held at Sourabaya

No. of Visits 16

First Date 13 - 9 1957

Last Date 28 - 11 19 57.

REPORT OF SHIP SURVEYS AND REPAIRS

The Surveyor's attention is drawn to the relevant requirements of Chapters B & C of the Rules.

No. in R.B.

04104

on the ~~BOGGA~~ Steel M.S.

"BOGGA"

Tons gross 193.

Year 8 - 1953.

Built at Spaarndam.

By Whom Spaarndammer Schps. Stapel.

When

Owners Republik Indonesia.

Owners' address (If not already in R.B.)

Managers Djawatan Pelajaran.

Port of Registry Djakarta.

Surveyed Afloat or in Drydock Drydock.

Name of Dock D.M.S.

Date of last examn. in Drydock 2.11.'57.

N.B.—Any alterations in existing particulars in the Register Book should be reported and underlined.

Last Report: No. 6074 To be filled in at Head Office.

Port SBA

Particulars of Classification (which must be inserted precisely as in Register Book and Supplement)

Surveys must be reported in the terms of the Rules. The nature and extent of Examinations and Repairs (if any) must be stated in detail, the parts examined and their condition being clearly indicated. For Annual, Special or other Condition Surveys the Summary of Examination and Condition on the back of the Report is to be carefully completed and amplified if necessary in the body of the Report. Outstanding items to complete the Survey should be summarised at the end of the Report. The reasons for Repairs must be stated. Repairs on account of Damage (the alleged cause of which must be stated) should be separated from Repairs due to other causes, and, besides being detailed in the body of the Report, should be summarised in the form below. When, at a Special Survey, the Shell and Deck Plating is drilled the results must be reported on Report 8(Dr). Whenever Anchors or Chain Cables are replaced or retested the necessary particulars are to be given on Report 8(Eq) which is to be attached to this Report.

SHIP'S CLASS Date of Special and of Drydocking Surveys, etc.

Machinery

+ 100A1

2/57

+ LMC.

N. 8/53 M. 8/55

CL. 9/56

Give dates and references to any letters relating to this Report.

In damage cases where the Surveyor has not made a special damage report he should state whether he offered his services for this purpose and to whom and why they were declined.

Freeboard as marked on ship and now verified 3 ft 4 1/4 ins

Was a damage report made by anyone else? If so, by whom?

EXAMINATION AND REPAIRS AS PER RULE FOR Special Survey (A) due 8/57. Ship 4 Years old, S.R.L.

Indented bottom plating dealt with now.

Port side A strake plate No. 3 between frames 448 1/2 and 551 1/2 renewed, plate No. A4 and A5 completely and plate No A6 between frames No.21 1/2 renewed. Port side B strake plates No.B3 and B4, completely and plate No.B5 between frames No.23 1/2 renewed. Frames No.31, 40 and 43 partly cut out, faired and refitted. Frames No.32,33,34,35,36,37,38,39,44 and 45 faired in place. Starboard side A strake plates No.3,4,5 and 6 completely renewed. Starboard side B strake plates No.B3 and B4 completely and B5 between frames No.22 1/2 and 27 1/2 renewed. Frame No.55 partly cut out, faired and re-fitted. Frames No.31,32,33,34,35,36,37,38 and 39 faired in place.

On completion of repairs d.b. tanks in way tested as required and all found sound and tight.

CONTINUATION OVER/OR SHEET 2

SUMMARY OF DAMAGE REPAIRS	Shell Plates	Frames	R. Frames	Floors and Bracket Floors	Inner Bottom Plates	Deck Plates	Beams	Other Items
Renewed								
Removed and Faired or Repaired								
Faired or Repaired in place								

Has a Survey also been held on machinery of the Ship? Yes. If so, is the Report sent now, or when will it be sent? Now.

Is Classification Certificate required? If so, to be sent to Sourabaya Surveyor. (2) Has Interim Certificate been issued? Yes.

GENERAL OBSERVATIONS, OPINION AND RECOMMENDATION AS TO CLASS

State clearly what alteration, if any, is suggested to be made in the existing Classification or Survey or other records of the Ship in the Register Book consequent upon this survey; for example:—"to remain as Classed in the Register Book without fresh record of Docking"; "to remain as Classed and to have record of drydocking 1.55"; or "to remain as Classed and to have record of drydocking 1.55, and the notation of S.S. . . . 1.55".

It is submitted this ship is eligible to be continued as classed with fresh record of S.S. 11.57 and D.S. 11.57 and have item indented and way bottom plating p & s be deleted from S.R.L.

Jacobs. Surveyor to Lloyd's Register of Shipping

Date of Committee

THURSDAY - 9 JAN 1958

Minute

DS 11.57 without apl. cond.

SS Sba. 11.57 ES 11.57

Note Sba. (to date)

Noted for Header

CERTIFICATE WRITTEN



© 2021

Lloyd's Register Foundation

012003-012010-0285

