

COPY

# Lloyd's Register of Shipping.

(UNITED WITH THE BRITISH CORPORATION REGISTER)

No. M-51916-A

Port

KOBE

5th September, 1958.

To LONDON

This is to Certify that

M. ISHIWATARI.

The undersigned Surveyor to this Society did at the request of Messrs. Nishishiba Denki K.K., attend their works at Himeji, on the 23rd July, 1958 and subsequently for the purpose of examining and witnessing tests on

Five (5) sets of 5/2 HP Three Phase Induction Motor for Cold Air Circulating Fan of Refrigerated Cargo Installation

intended for Ship No. 1532 being built by Nagasaki Works, Mitsubishi Shipbuilding & Engineering Co., Ltd., Nagasaki.

Particulars are as follows:-

A.C. 440V, 3φ, 3W, 60 cycles, 4/6 poles, 1800/1200 R.P.M.  
6.5/2.9A, cont. rating, Totally enclosed type with outside fan.  
Squirrel cage rotor and independent two stator windings  
Serial No. 58511253 to 6, and 58511271  
Lloyd's No. A.C.M. 1345 to 9

These motors were examined during construction in accordance with the Society's Rules and on completion, subjected to the following tests in the presence of undersigned, in the shop with satisfactory results.

Temperature rise test at rated load.

50% over load test for 1 min.

100% over load test for 15 sec.

25% over speed test for 1 min.

Insulation resistance test by 500V megger.

Dielectric test at A.C. 2000V for 1 min.

For identification purposes, these motor have been stamped as follows:-

On the body

No. 58511253 to 6  
or 58511271  
LLOYD'S KOB  
No. A.C.M. 1345 to 9  
MI 2-9-58 LR

On the shaft end

SE 9875A1 to 4  
or 9876E1  
LLOYD'S KOB  
No. KF2635-4 to 7  
or 2635-3  
MI LR KT  
23-7-58

Surveyor to Lloyd's Register.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-  
"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

(Rpt. 10) 1,60 KOB

MI:tw

Nagasaki Register  
Foundation

012036-012041-0043