

Nr	Description	Type	Dimension	Driven by	Capacity
1	1 Saltwater - coolingpump	B & W		Main motor	170 ts/h
2	1 Freshwater - coolingpump	"		"	170 ts/h
3	1 Lubricatingoil pump	"		"	170 ts/h
4	1 Bilgepump	"		"	20 ts/h
5	1 Sanitary pump	"		"	20 ts/h
6	1 Sparelubr.-oil pump	Eureka	9" x 12" x 10"	Steam 180 lbs	144 ts/h
7	1 Sparefrishw.-coolingpump	"	9" x 12" x 10"	"	144 ts/h
8	1 Ballastpump & sparesaltw.pump	"	9" x 12" x 10"	"	144 ts/h
9	1 Butterworthpump	Dawson & Downie	14" x 9" x 12"	"	"
10	1 Heater for Butterworth	Odense St.	16m ²	"	"
11	1 Bilge pump	"Eureka"	6" x 6" x 6"	"	30 ts/h
12	1 Sanitary pump	"	6" x 6" x 6"	"	30 ts/h
13	1 Transferpump for dieseloil	"	6" x 6" x 6"	"	30 ts/h
14	1 " " boileroil	"	4 1/2" x 4" x 4"	"	9 ts/h
15	1 Coolingw.-pump for refr.-plant	"	"	"	"
16	2 Boiler feed pump	"Eureka"	7 1/2" x 5 1/2" x 15"	Steam 180 lbs	9 ts/h
17	1 Freshwaterpump	"	3 1/2" x 2 1/2" x 3 1/2"	"	3 ts/h
18	1 Fan engine for oilburning plant	Howden	42"	Steam 100 lbs	12000 m/h
19	2 Starting air-compressors	Reawell	C.S.A. 7	Steam 100 lbs	2.5 m ³ /Min.
20	2 Dieseldynamos	Bukh	4D 160	Dieselmotor	44 kW 110 V
21	1 Electric main switchboard	D.E.C.			
22	1 Freshwater cooler	B & W	180 m ²		
23	1 Lubricatingoil cooler	"	180 m ²		
24	2 Main boilers	Stockton	2 x 150 m ²		
25	1 Exhaust boiler	Ralborg	125 m ²		
26	1 Lubricatingoil-purifier	Titan	Type 1800	Electr. Motor	3300 lit/hour
27	1 Dieseloil-purifier	"	"	"	5000 lit/hour
28	1 Preheater for lubricating oil	Odense St.	"	"	50 l.
29	1 " " dieseloil	"	"	"	50 l.
30	1 Startingair-receiver	B & W	"	"	18 m ³
31	1 Evaporator	"Eureka"	"	"	12 ts. pr 24h
32	1 Condenser	"	"	"	1000 sq. ft.
33	1 Lubricatingoil-filter	B & W	9"	"	"
34	1 Oilburning-plant	Swinney Bros	"	Steam 100 lbs	"
35	2 Boiler oil - settling tanks	Odense St.	"	"	2 x 5000 l.
36	2 Dieseloil - settling tanks	B & W	"	"	2 x 12500 l.
37	2 Tank for cylinderoil	Odense St.	"	"	2 x 4000 l.
38	2 " " lubricatingoil	"	"	"	2 x 4000 l.
39	1 " " cylinderoil (steam)	"	"	"	200 l.
40	1 " " compressoroil	"	"	"	300 l.
41	1 " " parafin oil	"	"	"	300 l.
42	1 " " waste lubricatingoil	"	"	"	200 l.
43	1 Ekspansions tank freshw. cooling	"	"	"	1000 l.
44	1 Feedwater well	"	"	"	"
45	1 Observation tank f. heating coils	"	"	"	"
46	1 2nd Silencer	B & W	"	"	"
47	1 Tetrochlorine cleaning device	"	"	"	"
48	1 Fuel oil handpump	"	"	"	"
49	1 Refrig. machinery	"	"	"	"
50	1 Travelling crane	Odense St.	"	"	"
51	1 Lifting block	Th. B. Thrige	"	Electr. Motor	5000 kg
52	1 " " " " " "	"	"	"	"
53	1 Lathe	South Bend	"	Electr. Motor	"
54	1 Drilling machine	Polar E 435	"	"	"
55	1 Grinding machine	S.M.9	"	Electr. Motor	"
56	1 Shaping machine	"	"	"	"
57	1 Handpump for lubricating oil	"	"	"	"
58	1 " " " " " "	"	"	"	"
59	1 Turning gear	B & W	"	Electr. Motor	"
60	1 Steamdynamo	Sunderland	"	Steam 120 lbs	20 kW 110 V
61	1 Boiler circulating pump	M & R E 250	"	Electr. Motor	200 lit/min.
62	1 Service tank	B & W	"	"	8250 l.
63	1 Spare-oil purifier	Titan	Type 1800	Electr. Motor	3300 lit/hour
64	1 Feedwater-heater	"	"	"	"
65	1 Draintank for fuel oil	B & W	"	"	250 l.


Odense Staalskibsværft A/S Maskinafdeling	Red Appr Tegnet 3-3-50 af Kontrol	Kl Appr Skala 1:50 D. 7.3.50 Chef RM
Machinery & Boiler Arrangement Floor		Bygn. Nr. 112 Gl. Nr. M 112.21 Nyt Nr.

"Charlotte Hearn" ★

Machinery & Boiler
Arrangement.

RECORDS DEPT.
LONDON

33



© 2021

Lloyd's Register
Foundation