

Lloyd's Register of Shipping,

(Reconnu par la Loi Belge sur la sécurité des Navires.)
(Arrêté Ministériel du 8 Janvier, 1921.)

Mersey House,
Quai de Rouen, 1,

Antwerp, 3rd September 1938.



Letters to be addressed to
SURVEYORS.

LLOYD'S REGISTER
Received
- 5 SEP 1938
Ansd.
LONDON

Dear Sirs,

With reference to your letter of the 1st instant respecting the freeboard of the S/S "GARBI" we have to inform you that all the conditions of freeboard assignment have been satisfactorily complied with, as follows:-

1. The flush bunker scuttles have permanent chain attachments.
2. Wooden plugs and canvas covers have been provided for closing the openings of the ventilator coamings and air pipes.
3. Hinged deadlights have been provided, where missing, for the forecandle side scuttles.
4. Rope lifelines have been supplied on the fore well port and starboard side.
5. Two new tarpaulins have been provided for the following hatchways:
Hatchway on forecandle deck to forecandle spaces
2 hatchways on bridge deck to bridge spaces.
hatchway on boat deck to coal shoot
hatchway on raised quarter deck to after peak.
6. One good and efficient tarpaulin has been provided for each of the four hatchways on the freeboard deck in the bridge space.
7. New hatch covers of Rule thickness have been fitted for each of the four hatchways on the freeboard deck in the bridge space, and for the two hatchways on the bridge deck to the bridge space.
8. Two air pipes (starboard side) to Nos. 1 & 2 Double bottom tanks have been renewed to 30" height.

-2-


It is regretted that these particulars were not forwarded with our verification of marking form.

We are, Dear Sir,

Yours faithfully,

The Surveyors,

per.-



The Secretary,

LONDON.



© 2021

Lloyd's Register
Foundation

012084-012095-0103

Handwritten notes and stamps on the right side of the page, including a vertical stamp that reads "Approved" and other illegible markings.

Referred to the Chief Ship Surveyor,
(Freeboard)

MB

5 SEP 1938

*Noted on light cv
MB
6/9/38*

LONDON

the secretary,



© 2022
Lloyd's Register
Foundation

bel..

the employees

some instances

we are, Dear Sir,

in connection of marking form.

It is referred that these markings were not followed

5-