

# LLOYD'S REGISTER OF SHIPPING

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "VASCO"

Official No. -

Port of Registry Cadiz

This ship has been under survey at S.E. de C. N. (Nervion), Bilbao

on 24.11.58 to 4,12 1958 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-

ACCESS HATCH TO Nos. 1 AND 2 HOLDS:-

Upper Deck (p.s. only):-

Access openings to Nos. 1 and 2 Holds now cut in Upper Deck on either side of frame 80 and within the line of hatch side girders. 12 m/m plate doubler fitted to deck plating in way of opening.

Size of deck openings:- 2 at 390 x 550 m/m.

Strongly constructed steel coaming 10 m/m in thickness and 915 m/m in height common to both access openings now fitted and electrically welded to deck doubler.

Closing appliances:- 75 m/m thick wood hatch covers, tarpaulins locking bars secured by 8 wedges.

*J. J. de la Haza*  
Surveyor to

Lloyd's Register of Shipping.

Noted  
AK  
9-2-59

A copy of this Report has been placed on board.

