

COPY.

Lloyd's Register of Shipping.



Port OF LIVERPOOL.

17th March, 1950.

This is to Certify that

T.J. ROBERTS.

the undersigned Surveyor to this Society did at the request of

The Owners Representative attend on board the S.S. "DOVER HILL" 7295 tons gross of Sunderland, whilst vessel afloat and loading in the Alexandra Dock, Liverpool, on the 15th March, 1950, and subsequently for the purpose of examining the closing plate fitted to shell over the original ash chute opening (Starboard).

On examination found the closing plate cut away and the part remaining of its original welded connection at its forward vertical edge found fractured.

It was stated that the welding at the after vertical edge of closing plate had also been found fractured.

Permanent Repairs now effected.

Shell openings slightly increased in size for the purpose of making well-rounded corners and a new insert plate 1" thick prepared with double vee edges, fitted and welded internally and externally and afterwards re-inforced with internal plate straps over weld.

and hose tested

Repair specially examined/on completion and found satisfactory.

Thos. J. Roberts

SURVEYOR TO LLOYD'S REGISTER.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly performed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances ever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."