

"TORNAGALEONES"

With reference to Valparaiso letter dated 24th May, 1963 and to copy of Owners letter attached thereto, it is submitted that the following requirements are necessary:-

(1) The Boiler and machinery subjects of class to be satisfactorily dealt with, these are:

- (a) Centre furnaces of the Port and Starboard Boilers to be renewed by June, 1961. The Boiler pressure meanwhile not to exceed 170lb. and all other furnaces being dealt with as necessary by June, 1961.
- (b) Main Engine steam pipe expansion piece to be examined and dealt with.
- (c) Ballast pump sea suction valve to be renewed at the next drydocking.

(2) Main Boiler Survey to be held.

(3) In addition to a General Examination as per Circular 1959 the Main Condenser should be tested and sea connections examined. Also Main Engine HP cylinder, piston, valve and gears, top and bottom ends and journals to be opened out and examined. If found satisfactory, no other machinery parts need be opened out for examination.

(4) The Screwshaft need not be drawn for examination providing the wear down is found satisfactory.

(5) A short sea trial to be held.

R.

30.5.63.



Lloyd's Register
Foundation

012324-012332-0177