

COPY.

" X A N T H U S "

22/6/33

PARTICULARS OF PUMPS.

<u>Description</u>	<u>No.off.</u>	<u>Type</u>	<u>Capacity Gallons per hour.</u>	<u>Position</u>	<u>Suctions</u>	<u>Discharges</u>
Bilge Pump.	1	Ram on Main Eng.	1000	Eng.Rm.Port.	Main Line Bilge.	Overboard
General Service	1	Steam Recipr.	3000	Eng.Rm.Port.	F.W.Tanks Sea.Direct Bilge & Main Line Bilge.	Deck Sanitary & Overboard.
Oil Transfer	1	Steam Recipr.	6000	Pump Room	Settling Tanks.	Settling tanks & deck.
Hand Bilge.	2	Hand deck lever type	6" diam. Barrel	Upper Deck.	Fore peak & Hold.	Overboard
Main Circ.	1	On main engine.	Approx. 3500	Engine Room Port.	Bilge Injection 4" diam. Main injection 5½" diam.	Overboard.



© 2021

Lloyd's Register
Foundation

012393-012400-0105