

KIEL, 7th May 1942.

"DIXIE HALL" ex "ACCOMPTON"

The Poop has been extended 8 meters further forward, the old bulkhead no longer intact and the new bulkhead of 8 mm plate with angle stiffeners 6" x 3" x $\frac{3}{8}$ " spaced 23" apart and intermediate D.A. stiffeners 3" x 3" x 7/16", all are bracketed top and bottom. There are two openings 32" x 20" closed by hinged steel w.t. doors capable of manipulation from both sides.

46