

# Lloyd's Register of Shipping.

Ship's Name S.S. "LLANGERN". Official No. 161133

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in \_\_\_\_\_

The following alterations have now been carried out:-

(1) Existing drain scuppers in tonnage well P. & S., now removed and openings in deck plating closed by S.W. closing plates. ✓ New 5" dia.

G.M.

Overboard scupper valves fitted, having screw down non-return valves, controlled from the shelter deck and fitted with indicators. ✓

(2) 3P & 3S existing overboard scuppers from the tween deck spaces now removed and openings in shell plating closed by S.W. spigoted closing plates. ✓

(3) 2P & 2S, 3" dia. drain scuppers fitted in 'tween deck spaces amidships, leading to the machinery space bilges and fitted with self closing cocks in accessible positions at the lower ends. ✓


Alterations examined on completion and found satisfactory. ✓

The former washport doors in the tonnage well were noted to have previously been closed permanently by S.W. ✓

*A.W.B. Edwards*

28.4.50.

SURVEYOR TO LLOYD'S REGISTER, HULL.



© 2001

Lloyd's Register  
Foundation

23 MAY 1950

012446 - 012459 - 0342