

29/3/27

DIMS:- 180' 0" B.P x 29' 3" MLD x 14' 0" MLD. 17-6 to R.Q.D.

TO CLASS LLOYDS 100 A.I. ✕

ST. LONGITUDINAL NO  $L \times D = 180 \times 14 = 2520$

$$2^{nd} \quad " \quad " \quad L \times (B+D) = 180 \times (29.25 + 14.0) = 7785$$

d. MAIN. DECK 11.5

d RAISED QUARTER DECK. 15.0

L/D. MAIN. DECK 12.85

1/2 RAISED QUARTER DK 10.28

FORECASTLE DECK STRINGER ANGLE, 3"x3"x.2G  
" " " PLATE 17"x.2G  
" " " SIDE PLATE .2G.

$$2^{\text{no}} \text{ NUMERAL} \cdot L \times (B+D) = \underline{7785}$$

RAISED QUARTER DECK  $50 \times 3.5 = 175$

BRIDGE  $51.33' \times 7.25' \times .75 = 279.106$

FILE  $23.5' \times 7.25' \times .75 = 127.781$

CASINGS  $34.23' \times 7.25' \times .5 = 126.758$

DECKHOUSE 12.83' x 7.25 x .5 46.5

Letter j EQUIPMENT NO 8540.145

2. BOWER ANCHORS 16<sup>3</sup>/<sub>4</sub> CWTs STOCK LESS

1	"	"	14 1/2	"	"
---	---	---	--------	---	---

1.	STREAM	"	4 <sup>3</sup> / <sub>4</sub>	"	EX STOCK
----	--------	---	-------------------------------	---	----------

210 FATHOMS 1 1/4" DIA STUD CHAIN CABLE


60 " 3" STEEL WIRE

75 " 2 3/4 " " " TOW LINE

30	"	6"	HEMP. HAWSER
4	"	4"	" WARP.

22500 2 1/4" STEEL WIRE

90	"	1 1/4	"	"
90	"	1 3/4	"	"



W.J.  
29.3.27.



No. 278.

Midship Section  
(approved plan)

Goole S.B. & R. Co. Ltd.

"Pireno"

Hull Y.E. Reg. No. 38483

012508-012513-0001



© 2021

Lloyd's Register  
Foundation