

Lloyd's Register of Shipping.

21 MAY 1943

Ship's Name GREATHOPE

Official No. 149415

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

additional accommodation for gunners in forecastle space starboard side
has been fitted at newcastle-on - Tyne.

1. Tonnage opening starboard side plated over and a 2" solid wood door fitted
4'-2" x 1'-11" clear opening, 18" sill, with sprung lock capable of being manipulated
from both sides.
2. 3'-10" dia portlights with strong deadlights fitted in forecastle space starboard side.
3. 1-6" dia cowl vent, 2'-6" coaming complete with wood plug and canvas cover.

Port side forecastle space. W.C. and wash place now fitted. W.C. discharge fitted
with automatic non-return valve at ship's side, 12" above freeboard deck.

cd copy of above has been placed on board vessel.

Noted J. S. R. 24 MAY 1943

Stephens P. Cooke
10-5-43