

TELEX FOR YOKOHAMA (19.4.66)

KOWA MARU YOUR LETTER FOURTEENTH APRIL FOR  
RECLASSIFICATION REQUIREMENTS OF SPECIAL SURVEY B  
TO BE COMPLIED WITH INCLUDING DRILLING OF STRUCTURE  
SUCH PARTS WHERE SIGNS OF WASTAGE ARE EVIDENT  
REFER C 205 OF THE RULES, ANY MAJOR REPAIRS OR  
STRUCTURAL ALTERATIONS WHICH HAVE BEEN EFFECTED TO  
THE STRUCTURE SINCE THE SHIP WAS DISCLOSED TO BE  
SPECIALLY EXAMINED IN ORDER TO ASCERTAIN THE CHARACTER  
OF WORKMANSHIP AND CONFIRM THAT MATERIALS USED ARE  
IN ACCORDANCE WITH THE RULES AND FULL PARTICULARS  
OF THE EQUIPMENT ON BOARD, INCLUDING WEIGHTS, TESTS  
AND CONDITION OF ANCHORS, ALSO LENGTH, DIAMETER, TESTS  
AND CONDITION ETC OF CHAIN CABLE TO BE FURNISHED FOR  
CONSIDERATION STOP REGARDS MACHINERY IT WILL BE  
NECESSARY TO CARRY OUT THE SCREWSHAFT SURVEY AND  
STEAMPIPE SURVEY <sup>AND SEE UNDER FOR MACHINERY SURVEY</sup> STOP IN VIEW OF SHIP HAVING BEEN  
BUILT TO CLASS IN OCTOBER 1959 A NOTATION OF  
RECLASSIFICATION CONTEMPLATED COULD BE ASSIGNED ON  
COMPLETION COMPREHENSIVE GENERAL EXAMINATION IF THIS  
WOULD MEET OWNERS REQUIREMENTS UNTIL FULL CLASSIFICATION  
REQUIREMENTS AS ABOVE COMPLIED WITH REGARDS MACHINERY  
FOR MACHINERY CLASSIFICATION CONTEMPLATED SATISFACTORY  
GENERAL EXAMINATION ALL MACHINERY AND BOILERS UNDER



WORKING CONDITIONS DURING SHORT SEA TRIAL AND  
WINDLASS AND PUMPING ARRANGEMENTS TRIED AND  
ELECTRICAL INSTALLATION MEGGER TESTED STOP IT IS  
CONCLUDED A COMPLETE AUXILIARY BOILER SURVEY WAS  
HELD BY NK LAST NOVEMBER STOP FOR FULL CLASSIFICATION  
OF MACHINERY THE EXTENT OF THE MACHINERY SURVEY  
WILL BE DECIDED WHEN NK RECORDS OF THEIR CSM ARE  
RECEIVED STOP THIS CONNECTION A COPY OF FORM 7E  
IS BEING FORWARDED SO THAT YOU CAN FILL IN THE  
SURVEY DATES STOP PARTICULARS OF ANY MAJOR  
ALTERATIONS OR RENEWALS SINCE AUGUST 1963 TO BE  
REPORTED

COMMITTEE



© 2021

Lloyd's Register  
Foundation

0071 2/2