

GLASGOW REPORT No. 74411a

Lloyd's Register of Shipping.

Ship's Name "BARON DOUGLAS"Official No. 161812

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

POOP

5 - 6" GOOSENECK VENTILATORS, 30" TO OPENING FROM DECK, WITH WOOD PLUGS & CANVAS COVERS FOR CLOSING. ✓

18 - 6" SCREW DOWN MUSHROOM VENTILATORS, COAMINGS 30" THICK, 30" HIGH WELDED TO DECK. ✓

12 - 6" COWL VENTILATORS, COAMINGS 30" THICK, 30" HIGH WELDED TO DECK, WITH WOOD PLUGS AND CANVAS COVERS FOR CLOSING. ✓

2 - 8" COWL VENTILATORS, COAMINGS 30" THICK, 30" HIGH, WELDED TO DECK WITH WOOD PLUGS AND CANVAS COVERS FOR CLOSING. ✓

4 - 12" COWL VENTILATORS, COAMINGS 40" THICK, 30" HIGH, WELDED TO DECK WITH WOOD PLUGS AND CANVAS COVERS FOR CLOSING. ✓

14 - 12" DIA. SIDELIGHTS HINGED TYPE OF BRASS FITTED WITH DEADLIGHTS & THUMBSCREWS TO M.O.T. REQUIREMENTS ✓

7 - 10" DIA. SIDELIGHTS HINGED TYPE OF BRASS FITTED WITH DEADLIGHTS & THUMBSCREWS TO M.O.T. REQUIREMENTS. ✓

A DECKHOUSE HAS BEEN FITTED FOR ACCESS TO CREWS' SPACE, BUILT OF STEEL WITH DOOR SILLS 18" HIGH AND 2 HARDWOOD DOORS, OPERABLE FROM BOTH SIDES, ALSO TUNNEL ESCAPE WITH STEEL W/T DOOR, OPERABLE FROM BOTH SIDES, AND 2 HINGED BUILT IN SKYLIGHTS, SECURED BY TOGGLES, ALL AS PER RULES AND APPROVED PLAN. ✓

2 HINGED SKYLIGHTS TO CREWS' SPACE SIMILAR TO THOSE BUILT INTO DECKHOUSE, SITUATED FORWARD OF HOUSE, SECURED BY TOGGLES. ✓

FORE & AFT WELLS

ACCESS DOORS TO NOS 1, 2, 4 & 5 HOLDS CUT IN MASTHOUSES ON FREEBOARD DECK HAVING SILLS 21" HIGH, AND STEEL W/T DOORS WITH TOGGLES OPERABLE FROM BOTH SIDES. ✓


FORECASTLE

TONNAGE OPENING CUT AT CENTRE OF FORECASTLE FRONT 5'-0" x 4'-0" WITH COAMING 18" HIGH WITH WEATHERBOARDS FITTED INTO CHANNELS FULL HEIGHT. WELDED OUTSIDE FORECASTLE FRONT. ✓

James F. Edgar.

Maked
31 AUG 1949

012610-012612-0012



© 2021

Lloyd's Register
Foundation