

Less Eng
Less Navig

Lloyd's Register of Shipping.

Port COLOMBO.

18th, October: 1922.

This is to Certify that

H. S. M e l t o n,

the undersigned Surveyor to this Society did at the request of

Messrs, The Anglo-Persian Oil Co., Ltd, have Surveyed the Bumb
Oil Barge, A. P. O. C. No.10 gross tons 205 during construct-
ion, and all Recommendations made by the Committee of the
above Society have been faithfully carried out by the Contract-
ors as per their Drawing No. 528.A. dated 13. 8. 21 and Speci-
fication dated the 16th August, 1921.

The above Barge was launched on the 3/8/22 and completed on
the 18/10/22, being designed to Carry Liquid Fuel in bulk
F.P. 150 F, for Harbour purpose entitling her to the letter
A in the Register Book.

Equipment:- to the Society's Recommendations further entitl-
ing her to the numeral 1.

All tanks were subject to a Water Test (eight feet head) and
found perfectly tight.

Cofferdams were water tested to my satisfaction.

Each Tank was separately calibrated in my presence as per
readings attached /



© 2021

Lloyd's Register
012646-012655-0022 ^{1/2}

Continued:-

2.

The variation in capacity being practically nil, estimated total capacity 278 tons Liquid Fuel.

At Pump trials roughly 275 tons were discharged in 55 minutes at the floor levels, limber holes in floors being too small to permit efficient flow, Recommended that these be enlarged which was done.

On leaving to Bombay. All hatchways and companion ways and ventilators opening were efficiently battened down.

All Deck-gears securely lashed. Deck side Scuppers left open.

No. 3 Tank was water ballasted, mean draught of the vessel on her departure being 4.11 10 $\frac{1}{2}$ ".

Special towing lugs were fitted to Port & Starboard Stringer angle in way of forward cofferdam of ample strength.

All materials used in the vessel's construction have been passed by the Society's Surveyors and the workmanship throughout has been to my entire satisfaction.

The Hull received one coat Red Lead and one each of Anti-corrosive and Anti-fouling paints, and the tanks special petrol resisting paint.

W. S. Mutton



© 2021

Lloyd's Register
Foundation

0022 ^{2/2}