

26 JUN 1944

fld. 2151.

Rpt. C. 11 (Contd.)

Index No. 35487

# Lloyd's Register of Shipping.

Ship's Name ~~"ANGLO-INDIAN"~~ LUCKY Official No. 166338

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations have now been carried out and found satisfactory:-

- In way of additional accommodation for gunners in starboard after tween decks
- 6 sidelights fitted, each 10" diameter, with hinged C.I. deadlights.
- 2 - 9" diameter ventilators fitted on upper deck, leading to new accommodation in tween decks, coamings 2'6" high 5/16" thick, with wood plugs & canvas covers.
- 1 - 24" diameter escape hatch from tween deck fitted on upper deck, with hinged bolted lid operated from both sides (Admiralty pattern).
- 1 - W.C. discharge and 1 washplace discharge fitted in tween decks, fitted with storm valve and non-return valve.
- A steel companionway of substantial construction, fitted on starboard side of upper deck, against existing sidehouse, and leading to new accommodation in tween decks. Door coaming 18" high, hinged wooden door & spring lock.

*A. W. B. Edwards*

Surveyor to

Lloyds Register of Shipping

Hull. 17/6/44

*Noted.*  
20 JUN 1944  
*J.P.S.*



© 2021

Lloyd's Register Foundation

012663-012668-0132.1