

24 FEB 1965

Ship's name CUTRAL CO.

B. AS
Port MVO.37083
No. 2296

Class is subject to —

Last survey date 27-11-64
16-12-64

- (1) M/E crankshaft centre coupling bolts being examined by 9/64 (12 nos)
- (2) End and aft (Nos 1 & 4) scavenge blower turbines being dealt with by 9/64 (6 nos)

Docking

Wear down after reworking 2.0 in.

CSM completed. ABS due 2/65, commenced 2/64 Not advanced

TS due 2/66 now held.

SRL Item (1) dealt with and to delete from the listItem (2) ast blower fitted with new nozzle plate, rotor and bearings

End blower fitted with new nozzle plate, rotor examined found to remain efficient until the rotor removed from the aft blower has been reconditioned. Item to be amended

to End scavenge blower rotor being dealt with as necessary by 5/65

The BAs Surveyor reports the M/E N° 5 cyl. cover found to have been repaired by drilling in way of porous section and fitted with 3/4" gas screwed plug. and afterwards seal welded. He recommends the M/E N° 5 cylinder cover be specially examined by 5/65 (6 nos)


The MVO Surveyor reports spare unused screw shaft fitted on account of wear on screw shaft liner of the original shaft. Other wear and tear repairs effected

It is submitted that this vessel is eligible for THE RECORD. — TS (CL) N 12/64
CSM 12/64

To Complete ABS —

ELC locker SV's & adjutant under steam.

Subject as amended re Item (2) and as recommended but without subject re Item (1)



© 2021

Lloyd's Register
Foundation

CERTIFICATE WRITTEN

26/1/65