

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER)

Ship's Name <b>'KANCHADEVA'</b>	Official Number ✓	Nationality and Port of Registry <b>SINGALESE</b> <b>COLOMBO</b>	Gross Tonnage <b>40</b> <i>Approx</i>	Date of Build <b>1959.</b>	Port of Survey <b>LOWESTOFT.</b>
Moulded Dimensions: Length <b>55'-6"</b> Breadth <b>15'-0"</b> Depth <b>8'-0"</b>					Date of Survey <b>DURING CONSTRUCTION</b>
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>87.5 91.0</b> tons					Surveyor's Signature <b>G.J. Talbot.</b>
Coefficient of fineness for use with Tables <b>.68</b> (Actual 0.563)					Particulars of Classification <b>100A1 For Towing Services within 10 miles of the coast of Ceylon.</b>

<b>Depth for Freeboard (D).</b> Moulded depth ... <b>8.00</b> Stringer plate ... <b>.25</b> ... <b>.02</b> Sheathing on exposed deck <b>2"</b> ... <b>.17</b> $T \left( \frac{L-S}{L} \right) =$ Depth for Freeboard (D) = <b>8.19</b>	<b>Depth correction.</b> (a) Where D is greater than Table depth $(D - \text{Table depth}) R = \frac{8.19 - 3.70}{4.49} \times \frac{55.5}{130} = +1.92$ (b) Where D is less than Table depth (if allowed) (Table depth - D) R = If restricted by superstructures ✓	<b>Round of Beam correction.</b> Moulded Breadth (B) <b>15'-0"</b> Standard Round of Beam = $\frac{B \times 12}{50} = 3.6$ Ship's Round of Beam = <b>3.5</b> Difference <b>.10</b> Restricted to Correction = $\frac{\text{Diff}}{4} \times \left(1 - \frac{S_1}{L}\right) = \frac{.10}{4} = +.03$
---	--	--

## DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...					
„ overhang ...					
R.Q.D. enclosed ...					
„ overhang ...					
Bridge enclosed ...					
„ overhang aft ...					
„ overhang forward ...					
F'cle enclosed ...					
„ overhang ...					
Trunk aft ...					
„ forward ...					
Tonnage opening aft ...					
„ „ forward ...					
Total ...					

FLUSH DECK

Standard Height of Superstructure \_\_\_\_\_

„ „ R.Q.D. \_\_\_\_\_

Deduction for complete superstructure \_\_\_\_\_

Percentage covered  $\frac{S}{L} =$  \_\_\_\_\_

„ „  $\frac{S_1}{L} =$  \_\_\_\_\_

„ „  $\frac{E}{L} =$  \_\_\_\_\_

Percentage from Table, Line A.  
(corrected for absence of forecastle (if required))

Percentage from Table, Line B.  
(corrected for absence of forecastle (if required))

Interpolation for bridge less than 2L (if required)

Deduction = \_\_\_\_\_

Designed Twin 1'-3" by Stern.

## SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate	S	M	Product
A.P. ...	<b>15.55</b> ✓	1		<b>15.55</b>	<b>32.625</b>	<b>8.88</b> ✓	1		<b>8.88</b>
$\frac{1}{8}$ L from A.P. ...	<b>6.92</b> ✓	4		<b>27.68</b>	<b>44.375</b>	<b>3.38</b> ✓	4		<b>13.52</b>
$\frac{2}{8}$ L „ ...	<b>1.71</b> ✓	2		<b>3.42</b>	<b>4.125</b>	<b>.38</b> ✓	2		<b>.76</b>
Amidships ...	<b>0</b>	4		<b>0</b>	<b>0</b>	<b>0</b>	4		<b>0</b>
$\frac{2}{8}$ L from F.P. ...	<b>3.42</b> ✓	2		<b>6.84</b>	<b>0.375</b>	<b>4.13</b>	2		<b>6.84</b>
$\frac{1}{8}$ L „ ...	<b>13.84</b> ✓	4		<b>55.36</b>	<b>3.375</b>	<b>4.38</b>	4		<b>55.36</b>
F.P. ...	<b>31.10</b>	1		<b>31.10</b>	<b>8.875</b>	<b>32.63</b>	1		<b>31.10</b>
Total ...				<b>139.95</b>	<b>32.625</b>				<b>116.46</b>

Mean actual sheer aft = **<.50** ✓

Mean standard sheer aft \_\_\_\_\_

Mean actual sheer forward = **EXCESS** ✓

Mean standard sheer forward \_\_\_\_\_

Length of enclosed superstructure forward of amidships = \_\_\_\_\_

„ „ aft of „ = \_\_\_\_\_

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( \frac{.75 - S}{2L} \right) = \frac{23.49}{18} (.75) = +.98$

If limited on account of midship superstructure. \_\_\_\_\_

If limited to maximum allowance of  $1\frac{1}{2}$  ins. per 100 ft. ✓

Deduction for Tropical Freeboard.  
Addition for Winter and Winter North Atlantic Freeboard.

Depth to Freeboard Deck = **8.19** ✓

Summer freeboard = **1.38** ✓

Moulded draught (d) = **6.81** ✓

Deduction for Tropical freeboard and addition for Winter freeboard =  $\frac{d}{4}$  inches = **1.70** ✓

Addition for Winter North Atlantic Freeboard (if required) = \_\_\_\_\_

Deduction for Fresh Water.

Displacement in salt water at summer load water line

$\Delta =$  **88.5 92**

Tons per inch immersion at summer load water line

$T =$  **1.62 1.64** ✓

Deduction =  $\frac{\Delta}{40T}$  inches = **1.43**  
= **1 1/2** ✓

TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient **NIL** ✓

Depth Correction ... **1.92** ✓

Deduction for superstructures ... **.98** ✓

Sheer correction ... **.03** ✓

Round of Beam correction ... **.03** ✓

Correction for Thickness of Deck amidships

Other corrections, scantlings, etc. ... **6.94** ✓

a summer moulded draught of **6.81 ft.** ✓

**5.80 + .83** ✓

**6.63**

**6.63**

Summer Freeboard = **16.50** ✓

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:

Tropical Fresh Water Line above Centre of Disc ...	<b>3 1/4</b> ✓
Fresh Water Line „ „ ...	<b>1 1/2</b> ✓
Tropical Line „ „ ...	<b>1 3/4</b> ✓
Winter Line below „ „ ...	<b>—</b>
Winter North Atlantic Line „ „ ...	<b>—</b>

Tropical Fresh Water Freeboard ...	<b>1'-4 1/2"</b> ✓
Fresh Water „ „ ...	<b>1'-1 1/4"</b> ✓
Tropical „ „ ...	<b>1'-3"</b> ✓
Winter „ „ ...	<b>1'-2 3/4"</b> ✓
Winter North Atlantic „ „ ...	<b>not assigned</b>



A circular library stamp from the University of Michigan Library, featuring the text "UNIVERSITY OF MICHIGAN LIBRARY" around the perimeter.

Names of sister ships.....None

Owners. Brown Agents for the Colonies, 4, Leic Bank, London S.W.1.

Fee £ 9 0 0